

**SUMMARY OF QUANTITIES (Cont'd)**

SHEET 2 OF 2

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	*	MACON	51	5

• (126X) RS-1&135 (R) RS&(BR-1) BRJ  
CONTRACT NO. 90926

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	LOCATION OF WORK:	
					URBAN STA. 1024+00 TO STA. 45+58 80% FED. 20% STATE 1000-2A	URBAN S. N. 058-0050 IL 48 OVER SPRING CREEK 80% FED. 20% STATE SFTY-2A
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701		L SUM	1.0	1.0	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801		L SUM	1.0	1.0	
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	3,168.0	3,168.0	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	2,247.0	2,247.0	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"		FOOT	30,543.0	30,543.0	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"		FOOT	1,915.0	1,915.0	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"		FOOT	1,866.0	1,866.0	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"		FOOT	1,423.0	1,423.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	18,080.0	18,080.0	
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	2,122.0	2,122.0	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"		FOOT	30,015.0	30,015.0	
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"		FOOT	1,567.0	1,567.0	
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"		FOOT	2,446.0	2,446.0	
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"		FOOT	1,214.0	1,214.0	
*78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	125.0	125.0	
*78001110	PAINT PAVEMENT MARKING - LINE 4"		FOOT	528.0	528.0	
*78001130	PAINT PAVEMENT MARKING - LINE 6"		FOOT	348.0	348.0	
*78001150	PAINT PAVEMENT MARKING - LINE 12"		FOOT	128.0	128.0	
*78001180	PAINT PAVEMENT MARKING - LINE 24"		FOOT	209.0	209.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH	455.0	455.0	
*88600100	DETECTOR LOOP, TYPE I		FOOT	6,663.0	6,663.0	
X0301424	SILICONE JOINT SEALER		FOOT	231.5		231.5
X0320887	POLYMER CONCRETE		CU FT	15.0		15.0
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E",		TON	6,660.0	6,660.0	
X4066658	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0,N90		TON	1,730.4	1,730.4	
X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90		TON	2,766.0	2,766.0	
X4401705	PARTIAL DEPTH REMOVAL		SQ YD	35.0	35.0	
X6060500	CORRUGATED MEDIAN REMOVAL		SQ FT	696.0	696.0	
X7015005	CHANGEABLE MESSAGE SIGN		CAL DA	100.0	100.0	
X7240600	REMOVE AND RE-ERECT EXISTING SIGN		EACH	5.0	5.0	
Z0004800	BITUMINOUS MIXTURE FOR PATCHING		TON	126.0	126.0	
Z0006110	BRIDGE DECK MICROSILICA CONCRETE OVERLAY		SQ YD	1,014.0		1,014.0
Z0010900	COLD MILLING (SPECIAL)		FOOT	3,731.0	3,731.0	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)		SQ YD	2.0		2.0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)		SQ YD	42.0		42.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE		L SUM	1.0	1.0	
Z0070100	SURVEY MONUMENT COVER ASSEMBLY		EACH	8.0	8.0	
*SPECIALITY ITEMS						