

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	5R, Y, RS-1	CLAY	376	6

STA. TO STA.
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

CONTRACT No 94367

80% FED.
20% STATE

CODE NO.	ITEM	UNITS	1000	TOTAL
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	0 2
54248510	CONCRETE COLLAR	CU YD	8.4	0 8.4
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	98	0 98
542A1909	PIPE CULVERTS, CLASS A, TYPE 3 24"	FOOT	104	0 104
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	48	0 48
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	28	0 28
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	869	0 869
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	221	0 221
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	255	0 255
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	42	0 42
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	74	0 74
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	97	0 97
542D0015	PIPE CULVERTS, CLASS D, TYPE 2 15" (TEMPORARY)	FOOT	412	0 412
542D0024	PIPE CULVERTS, CLASS D, TYPE 2 24" (TEMPORARY)	FOOT	88	0 88
542D0030	PIPE CULVERTS, CLASS D, TYPE 2 30" (TEMPORARY)	FOOT	29	0 29
542D0036	PIPE CULVERTS, CLASS D, TYPE 2 36" (TEMPORARY)	FOOT	30	0 30
63200310	GUARDRAIL REMOVAL	FOOT	400	0 400
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	114	0 114
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	19	0 19
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	0 9
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	9	0 9
67000600	Mobilization	L SUM	1	0 1
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2	0 2
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	0 1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0 1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0 1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0 1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0 1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	0 1
70106700	TEMPORARY RUMBLE STRIP	EACH	6	0 6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	700	0 700
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26197	0 26197
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	328	0 328
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	3140	0 3140
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	240	0 240
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	39488	0 39488
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	219	0 219
A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	50	0 50
A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	50	0 50
A2002316	TREE, BETULA NIGRA (RIVER BIRCH), 2" CALIPER, BALLED AND BURLAPPED	EACH	50	0 50
A2003316	TREE, FRAXINUS AMERICANA (WHITE ASH), 2" CALIPER, BALLED AND BURLAPPED	EACH	50	0 50

**

80% FED.
20% STATE

CODE NO.	ITEM	UNITS	1000	TOTAL
A2005416	TREE, LIRIODENDRON TULIPIFERA (TULIP TREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	50	0 50
A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	25	0 25
A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	50	0 50
A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	25	0 25
A2007616	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED	EACH	50	0 50
B2001116	TREE, CERCIIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	50	0 50
B2001316	TREE, CORNUS FLORIDA (FLOWERING DOGWOOD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	50	0 50
C2003024	SHRUB, FORSYTHIA NORTHERN SUN/NORTHERNSUN BORDER FORSYTHIA) 2' HEIGHT, BALLED AND BURLAPPED	EACH	20	0 20
D2002924	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 2' HEIGHT, BALLED AND BURLAPPED	EACH	50	0 50
X0321100	GEOTEXTILE RETAINING WALL	SO FT	7	0 7
X0322871	MAINTENANCE OF EROSION CONTROL SYSTEM	LSUM	1	0 1
X3550400	BITUMINOUS BASE COURSE, SUPERPAVE, 7"	SO YD	13961	0 13961
X3550500	BITUMINOUS BASE COURSE, SUPERPAVE, 8"	SO YD	4234	0 4234
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	2448	0 2448
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	206	0 206
X4073151	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/2"	SO YD	43963	0 43963
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TONS	193	0 193
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	0 1
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	0 1
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	0 1
Z0007604	BUILDING REMOVAL NO. 4	L SUM	1	0 1
Z0007605	BUILDING REMOVAL NO. 5	L SUM	1	0 1
Z0007606	BUILDING REMOVAL NO. 6	L SUM	1	0 1
Z0007607	BUILDING REMOVAL NO. 7	L SUM	1	0 1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0 1
Z0022800	FENCE REMOVAL	FOOT	6969	0 6969
Z0023900	FILLING EXISTING WELLS	EACH	1	0 1
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	9	0 9
Z0030200	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	30	0 30
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	0 2
Z0054505	ROCK FILL (REPLACEMENT)	TON	278	0 278
Z0076600	TRAINEES	HOURS	1000	1000
X5400503	PRECAST CONCRETE BOX CULVERT 3' X 3' (TEMPORARY)	FOOT	8	0 8
X5400504	PRECAST CONCRETE BOX CULVERT 4' X 2' (TEMPORARY)	FOOT	14	0 14
X5400510	PRECAST CONCRETE BOX CULVERT 10' X 6' (TEMPORARY)	FOOT	8	0 8
X5400450	BOX CULVERT END SECTION, CULVERT NO. 12B	EACH	2	0 2
X4420115	PAVEMENT PATCH TYPE IV, (SPECIAL)	SO YD	2427	0 2427

○ 8FTY-3N
△ Y080
** SPECIALTY ITEMS

△ Rev. 2-24-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE: 12/14/04 DRAWN BY: JJC CHECKED BY: WHG