

CONTRACT No 94367

FURNISHING AND INSTALLING PROPERTY MARKERS LOCATIONS						
North	East	Station	Offset*	Req.	Description	Each
794,202.79	933,139.97	1048+47.53	111.79	Iron Pin	Property Corner	1
788,833.96	934,471.86	1104+49.02	-176.05	Iron Pin	W/4 Cor 35-5N-6E	1
786,161.78	934,407.24	1131+53.67	19.35	Iron Pin	NE Cor 3-4N-6E	1
786,160.90	934,433.63	1131+53.87	-7.05	Iron Pin	SW Cor 35-5N-6E	1
786,005.26	934,183.61	1133+15.35	238.99	Iron Pin	Property Corner	1
785,997.20	934,392.19	1133+18.52	30.27	Iron Pin	Property Corner	1
785,995.79	934,433.68	1133+18.96	-11.24	PK Nail	Reference Corner	1
785,822.41	934,388.61	1134+93.22	30.14	Iron Pin	Property Corner	1
785,820.80	934,433.23	1134+93.96	-14.51	Iron Pin	Reference Corner	1
TOTAL						9

\* (+) right and (-) left

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS				
US 45	LT/RT	OFFSET (FT)	EACH	
982+89.12	LT	60	1	
992+72.77	RT	60	1	
1000+00.00	LT	60	1	
1000+50.00	LT	90	1	
1001+00.00	LT	90	1	
1001+50.00	LT	60	1	
1003+06.83	RT	60	1	
1003+06.83	LT	60	1	
1005+76.50	RT	200	1	
1005+79.25	RT	60	1	
1005+95.55	RT	80	1	
1006+47.59	RT	215	1	
1006+73.89	RT	80	1	
1006+97.98	RT	60	1	
1007+36.96	LT	60	1	
1010+00.00	RT	60	1	
1010+50.00	RT	85	1	
1011+42.23	RT	85	1	
1012+00.00	RT	60	1	
1017+59.41	LT	60	1	
1019+24.07	RT	60	1	
1019+95.00	LT	60	1	
1020+19.46	LT	80	1	
1020+42.71	LT	190	1	
1020+60.83	LT	187	1	
1020+97.21	LT	182	1	
1020+98.03	LT	80	1	
1021+15.00	LT	60	1	
1027+70.39	LT	60	1	
1034+90.56	LT	70	1	
1037+00.00	RT	110	1	
1038+25.39	RT	170	1	
1040+00.00	LT	170	1	
1040+00.00	RT	170	1	
1041+50.00	RT	112	1	
1043+00.00	LT	170	1	
1045+00.00	LT	110	1	
1047+30.26	RT	320	1	
1047+40.00	RT	112	1	
1047+76.89	RT	312	1	
1048+50.00	RT	300	1	
1048+50.00	RT	140	1	
1049+50.00	RT	140	1	
1050+02.68	RT	112	1	
1051+00.00	LT	110	1	
1053+74.62	LT	65	1	
1062+43.85	LT	65	1	
1062+68.40	LT	85	1	
1062+71.40	LT	210	1	
1062+86.40	LT	210	1	
1063+26.41	LT	210	1	
1063+38.42	LT	85	1	
1063+41.42	LT	210	1	
1070+00.00	LT	65	1	
1070+50.00	LT	120	1	
1072+50.00	LT	120	1	
1073+00.00	LT	65	1	
1075+71.41	RT	106	1	
1075+83.78	RT	150	1	
1075+87.65	RT	125	1	
1076+01.86	RT	155	1	
1076+37.78	RT	165	1	
1076+55.61	RT	170	1	
1076+63.68	LT	65	1	
1076+64.18	RT	125	1	
1076+87.96	RT	103	1	
1088+50.00	LT	65	1	
1089+00.00	LT	80	1	
1090+00.00	LT	80	1	
1090+50.00	LT	60	1	
1092+81.36	LT	60	1	
1097+50.00	LT	60	1	
1098+00.00	LT	60	1	
1101+66.36	RT	69	1	
1103+17.19	RT	210	1	
1103+37.67	RT	210	1	
1103+40.36	RT	105	1	
1103+65.00	LT	50	1	
1103+77.80	LT	60	1	
1103+78.62	RT	210	1	
1103+99.10	RT	210	1	
1104+26.46	LT	260	1	
1104+27.72	RT	80	1	

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS				
US 45	LT/RT	OFFSET (FT)	EACH	
1104+47.04	LT	260	1	
1104+50.00	RT	60	1	
1104+75.57	LT	60	1	
1104+88.21	LT	260	1	
1105+00.00	LT	50	1	
1105+24.23	LT	260	1	
1110+10.06	RT	60	1	
1111+58.27	LT	60	1	
1116+02.92	LT	60	1	
1116+02.92	RT	60	1	
1120+00.00	LT	60	1	
1121+00.00	RT	60	1	
1122+50.37	RT	120	1	
1122+50.37	LT	120	1	
1125+00.00	RT	120	1	
1125+00.00	LT	120	1	
1127+00.00	LT	85	1	
1127+50.00	RT	60	1	
1131+05.00	LT	85	1	
1131+26.38	LT	140	1	
1131+27.91	LT	260	1	
1131+47.81	LT	260	1	
1131+82.80	LT	260	1	
1132+07.85	LT	260	1	
1132+11.08	LT	105	1	
1132+25.00	LT	85	1	
1141+91.23	RT	60	1	
1141+91.23	LT	85	1	
1143+00.00	LT	60	1	
1143+40.00	RT	60	1	
TOTAL			114	

TEMPORARY CONCRETE BARRIER (STATE OWNED)					
U.S. 45	Stage	FOOT			
1034+00.00	to 1036+00.00	52'-62' RT	1-C	200	
1034+30.00	to 1036+00.00	12' RT	2-A	170	
1048+74.00	to 1049+74.00	12' RT	1-C	100	
1055+50.00	to 1057+00.00	12' RT	2-A	150	
1055+50.00	to 1057+00.00	59' to 44' R	1-C	150	
1070+50.00	to 1071+50.00	12' RT	1-C	100	
1096+40.00	to 1097+20.00	12' RT	1-C	80	
1122+00.00	to 1127+50.00	13' LT	1-A	550	
Stage Construction of Culverts					
1142+00.00	to 1143+00.00	LT	1-A	100	
1141+25.00	to 1143+65.00	CL	1-A	240	
Detour 1					
988+50.00	to 989+50.00	LT/RT	1-B	200	
1000+62.00	to 1001+62.00	RT	1-B	100	
Detour 2					
1122+00.00	to 1127+50.00	RT	1-B	550	
1122+50.00	to 1127+00.00	RT	1-B	450	
TOTAL				3140	

TEMPORARY RUMBLE STRIP		
LOCATION		EACH
Stage Const Box Culvert Sta 1142+45		
1122+01.00	RT	1
1127+01.00	RT	1
1132+01.00	RT	1
1152+92.00	LT	1
1157+92.00	LT	1
1162+92.00	LT	1
TOTAL		6

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), TEST LEVEL 3		
LOCATION		EACH
US 45		
1034+30.00	Rt	1
1036+00.00	Rt	1
1034+30.00	Rt	1
1036+00.00	Rt	1
1048+74.00	Rt	1
1049+74.00	Rt	1
1055+50.00	Rt	1
1057+00.00	Rt	1
1055+50.00	Rt	1
1057+00.00	Rt	1
1070+50.00	Rt	1
1071+50.00	Rt	1
1096+40.00	Rt	1
1097+20.00	Rt	1
1122+00.00	Lt	1
1127+50.00	Lt	1
Stage Construction of Culverts		
1142+00.00	Lt	1
1143+00.00	Lt	1
1141+25.00	Cl	1
1143+65.00	Cl	1
Detour 1		
988+59.00	Lt/Rt	2
989+59.00	Lt/Rt	2
1000+62.00	Rt	1
1001+62.00	Rt	1
Detour 2		
1122+00.00	Rt	1
1127+50.00	Rt	1
1122+50.00	Lt	1
1127+00.00	Lt	1
Total		30

PERMANENT SURVEY MARKERS, TYPE I		
LOCATION		EACH
984+51.99		1
1003+06.83		1
1011+42.23		1
1016+19.32		1
1023+23.16		1
1027+70.39		1
1034+90.56		1
1053+74.62		1
1062+43.85		1
1072+67.24		1
1078+56.24		1
1087+96.83		1
1092+81.36		1
1110+10.60		1
1115+51.02/1116+02.92		1
1122+50.36		1
1131+47.81		1
1132+15.29		1
1141+91.23		1
TOTAL		19

SHORT-TERM PAVEMENT MARKING			
U.S. 45		NO. OF APPLICATIONS	FOOT
968+00.00	to 980+00.00	4	480
1138+00.00	to 1143+50.00	4	220
TOTAL			700

PAINT PAVEMENT MARKING - LINE 4"			
LOCATION	TYPE		FOOT
968+00.00	to 1143+50.00	solid white	35100
		yellow 10' spaced @ 30'	4388
TOTAL			39488

RAISED REFLECTIVE PAVEMENT MARKER		
U.S. 45		EACH
968+00.00	to 1143+50.00	219
TOTAL		219

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3		
LOCATION		EACH
Stage Construction of Culverts		
1141+25.00	Cl	1
1143+65.00	Cl	1
Total		2

TEMPORARY PAVEMENT MARKING - LINE 4"			
LOCATION	TYPE		FOOT
Detour 1			
00+00.00	to 33+62.11	white	6724
		solid yellow	6724
Detour 2			
00+00.00	to 29+41.10	white	5882
		solid yellow	5882
Stage Const Box Culvert Sta 1142+45			
LT - Stage 1-A (Phase 1)			
1141+53.00	to 1143+40.00	solid yellow	187
1140+85.00	to 1144+05.00	white	320
RT - Stage 1-A (Phase 2)			
1141+65.00	to 1143+22.00	solid yellow	157
1140+85.00	to 1144+05.00	white	320
Total			26197

WORK ZONE PAVEMENT MARKING REMOVAL			
LOCATION	Line Width		SQ FT
Stage Const Box Culvert Sta 1142+45			
LT - Stage 1-A (Phase 1)			
1141+53.00	to 1143+40.00	CL	62
1140+85.00	to 1144+05.00	LT	107
RT - Stage 1-A (Phase 2)			
1141+65.00	to 1143+22.00	CL	52
1140+85.00	to 1144+05.00	RT	107
TOTAL			328

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

# SCHEDULE OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE: 12/14/04

DRAWN BY: JJC  
CHECKED BY: WHG