

CULVERT SUMMARY

94367

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	5R, Y, RS-1	CLAY	376	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	STATION	PIPE CULVERTS CLASS A				PIPE CULVERTS CLASS D						END SECTIONS					
		TYPE 1 EQRS 24" (FOOT)	TYPE 1 EQRS 30" (FOOT)	TYPE 1 24" (FOOT)	TYPE 3 24" (FOOT)	TYPE 1 15" (FOOT)	TYPE 2 15" (FOOT)	TYPE 1 18" (FOOT)	TYPE 1 24" (FOOT)	TYPE 2 24" (FOOT)	TYPE 1 30" (FOOT)	15" (EACH)	18" (EACH)	24" (EACH)	30" (EACH)	PRC FES 24" (EACH)	PRC FES EQRS 24" (EACH)
ENTRANCES																	
	982+34.10 RT							68									
	991+28.95 LT					43											
	1010+11.66 LT					50											
	1010+50.00 RT					36											
	1020+40.07 RT					36											
	1024+79.53 RT					36											
	1033+71.19 LT																
	1052+00.00 LT					44			97	42							
	1057+73.59 LT					47											
	1064+85.03 LT					43											
	1069+79.54 RT																
	1082+19.32 LT					60											
	1082+19.32 RT					57											
	1086+63.29 RT					36											
	1094+13.20 LT					44											
	1096+13.07 RT																
	1099+00.00 RT					43											
	1108+48.38 LT					44											
	1113+30.50 LT					56											
	1117+23.30 RT																
	1119+64.18 RT																
	1127+86.78 LT																
	1132+80.91 RT					47											
	1134+82.18 RT					41											
	1140+15.61 LT																
	1140+67.23 RT																
	1140+67.23 RT																
SIDE ROADS																	
TR 1725 N	9+00.00					40											
TR 1725 N	9+63.89	48															
TR 1700 N	10+37.24			48													
TR 1650 N	9+28.00				104												
TR 1550 N	9+60.00			50													
TR 1550 N	12+50.00					34											
TR 1550 N	11+22.00					32											
TR 1550 N	11+58.00			28													
TR 1550 N	11+97.91																
GRAND TOTALS		48	28	98	104	869	74	221	255	97	42	42	10	10	2	6	2

CULVERT NO./ LOCATION	STATION	PORUS GRANULAR EMBANKMENT (CU YD)	ROCK FILL REPLACEMENT (TON)	PRECAST BOX CULVERT SIZE								END SECTIONS								CAST IN PLACE
				2'x2' (FOOT)	3'x2' (FOOT)	3'x3' (FOOT)	4'x2' (FOOT)	4'x4' (FOOT)	5'x5' (FOOT)	7'x7' (FOOT)	10'x6' (FOOT)	12'x12' (FOOT)	2'x2' (EACH)	3'x2' (EACH)	3'x3' (EACH)	4'x2' (EACH)	4'x4' (EACH)	5'x5' (EACH)	7'x7' (EACH)	
MAIN LINE																				
2	984+34.00							84												
3	989+09.00							90												
4	997+02.00																			
5	1001+12.00																			
6	1011+16.00																			
7	1040+19.21		278			58														
8	1049+24.00																			
9	1071+00.00																			
10	1077+75.00							90												
11	1089+70.55																			
12	1096+70.00																			
12B	1104+40.00																			
13	1123+70.00																			
14	1142+45.00																			
14	1142+45.00	81																		
GRAND TOTALS		81	278	90	200	174	216	114	102	162	144	102	2	6	4	8	2	2	2	2

LOCATION	STATION	TEMPORARY PIPE CULVERT SCHEDULE PIPE CULVERTS CLASS D				TEMPORARY PRECAST BOX CULVERT		
		TYPE 2 15" (FOOT)	TYPE 2 24" (FOOT)	TYPE 2 30" (FOOT)	TYPE 2 36" (FOOT)	PRECAST BOX CULVERTS 3'x3' (FOOT)	PRECAST BOX CULVERTS 4'x2' (FOOT)	PRECAST BOX CULVERTS 10'x6' (FOOT)
ENTRANCES								
	979+53.42 RT							
	982+34.10 RT	20						
	986+09.54 RT		20					
	991+28.95 RT	16						
	999+34.40 RT	16						
	1004+91.23 LT	16						
	1006+50.26 LT	26						
	1010+11.66 LT	18						
	1014+49.61 LT	22						
	1024+79.53 RT	16						
	1063+00.00 RT	26						
	1064+85.03 RT	24						
	1084+56.50 RT	17						
	1086+63.29 RT	16						
	1092+40.21 RT	24						
	1099+78.51 RT	34						
	1113+30.50 LT	16						
	1119+64.18 LT	20						
	1127+86.78 LT	24						
	1129+47.33 LT	16						
	1134+82.16 LT	17						
TOTALS		412	88	29	30	8	14	8

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<h2>SCHEDULE OF QUANTITIES</h2> <p>SCALE: VERT. HORIZ. DATE: 12/14/04</p> <p>DRAWN BY: JJC CHECKED BY: WHG</p>

11/14/04 10:53 AM