

94367

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	5R, Y, RS-1	CLAY	376	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVING SUMMARY

STATION	PROCESSING LIME MODIFIED SOILS 12"	SUB-BASE GRANULAR MATERIAL, TYPE B	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS BASE COURSE, SUPERPAVE, 7"	BITUMINOUS BASE COURSE, SUPERPAVE, 8"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/2"	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	AGGREGATE SHOULDERS, TYPE B, 8"	BITUMINOUS SHOULDERS SUPERPAVE, 8"	PAVEMENT PATCH, TYPE IV (SPECIAL)	BITUMINOUS MIXTURE COMPLETE
	SQ YD	TON	TON	GALLON	SQ YD	SQ YD	TON	(TON)	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON
<i>U.S. 45</i>														
967+50.00 to 980+00.00			7.2	270.8			304.8				1053.6	800.0		
980+00.00 to 984+51.99	1356.0							145.6	1261.8		473.2	301.3		
984+51.99 to 1003+06.83	4664.5	600.0							5178.1		2011.8	1236.6	866.7	
1003+06.83 to 1011+42.23	2506.2								2332.2		859.2	556.9		
1011+42.23 to 1016+19.32	1431.3								1331.9		501.9	318.1		
1016+19.32 to 1023+23.16	1886.2	380.0							1964.9		734.7	469.2	548.9	
1023+23.16 to 1027+70.39	1341.7								1248.5		482.8	298.2		
1027+70.39 to 1034+90.56	2160.5								2010.5		800.2	480.1		3.6
1034+90.56 to 1053+74.62	5652.2								5259.7		2046.9	1256.0		4.3
1053+74.62 to 1062+43.85	2607.7								2426.6		965.8	579.5		7.9
1062+43.85 to 1072+67.24	3070.2								2857.0		1087.5	682.3		
1072+67.24 to 1078+56.24	1767.0								1644.3		622.8	392.7		
1078+56.24 to 1087+96.83	2821.8								2625.8		1015.7	627.1		
1087+96.83 to 1092+81.36	1453.6								1352.6		512.5	323.0		
1092+81.36 to 1110+10.60	4819.6	700.0							4827.5		1793.3	1152.8	1011.1	
1110+10.60 to 1115+51.02	1621.3								1508.7		586.4	360.3		
1116+02.92 to 1138+00.00	6591.2								6133.5		2370.4	1464.7		21.7
1138+00.00 to 1143+50.00			3.2	119.2			134.1	60.7		390.2	488.9	366.7		
<i>Detour 1</i>														
02+00.00 to 20+30.06					4592.0		504.9							7.9
20+30.06 to 21+63.68					335.3		36.9							
21+63.68 to 24+58.72					740.3		81.4							
24+58.72 to 26+44.01					464.9		51.1							3.9
26+44.01 to 28+99.15					640.2		70.4							
28+99.15 to 30+94.00					488.9		53.8							
<i>Detour 2</i>														
01+22.00 to 01+45.61					59.2		6.5							
01+45.61 to 02+26.42					202.8		22.3							
02+26.42 to 03+61.67					339.4		37.3							
03+61.67 to 25+56.95					5508.4		605.7							39.4
25+56.95 to 26+86.54					325.2		35.8							
26+86.54 to 27+70.16					209.8		23.1							
27+70.16 to 27+92.00					54.8		6.0							
SUBTOTAL	45751	1680	10	390	13961	0	1974	206	43963	390	18407	11665	2427	89

STATION	PROCESSING LIME MODIFIED SOILS 12"	SUB-BASE GRANULAR MATERIAL, TYPE B	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS BASE COURSE, SUPERPAVE, 7"	BITUMINOUS BASE COURSE, SUPERPAVE, 8"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/2"	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	AGGREGATE SHOULDERS, TYPE B, 8"	BITUMINOUS SHOULDERS SUPERPAVE, 8"	PAVEMENT PATCH, TYPE IV (SPECIAL)	BITUMINOUS MIXTURE COMPLETE
	SQ YD	TON	TON	GALLON	SQ YD	SQ YD	TON	(TON)	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON
<i>SIDERROADS</i>														
Twp Rd 950E 1725N						418	47							
1006+50.30 RT														
Twp Rd 960E 1700N						492	55							
1020+41.93 LT														
Twp Rd 975E 1650N						639	72							
1048+01.46 RT														
Twp Rd 975E 1625N						530	59							
1063+01.37 LT														
Twp Rd 975E 1600N						416	47							
1076+49.20 RT														
Jala Road														
1104+04.37 RT														
1104+04.37 LT						1092	122							
Twp Rd 1000E 1500N														
1131+54.81 LT						647	72							
SUBTOTAL	0	0	0	0	0	4234	474	0	0	0	0	0	0	0
GRAND TOTAL	45751	1680	10	390	13961	4234	2448	206	43963	390	18407	11665	2427	89

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY: JJC
 HORIZ. CHECKED BY: WHG
 DATE: 12/14/04