

94267

# ENTRANCE SUMMARY

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	5R, Y, RS-1	CLAY	376	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ENTRANCE SCHEDULE										
TYPE	SIDE / STATION	WIDTH	LENGTH		RADI	AGGREGATE BASE COURSE TYPE B	AGGREGATE SURFACE COURSE TYPE B	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	PCC DRIVEWAY PAVEMENT	
			u	L <sub>2</sub>		TON	TON	TON	SQ YD	
PE	RT	979+53.42	16'	20'	36'	20'	13.6	21.1	6.8	
PE	LT	980+92.65	14'	20'	10'	20'	12.3	5.3	6.2	
PE	RT	982+34.10	12'	20'	52'	20'	11.1	23.2	5.6	
PE	LT	986+09.54	24'	20'	14'	20'	18.6	12.2	9.4	
FE	RT	986+59.15	20'	30'	37'	30'		48.5		
PE	LT	991+28.95	12'	20'	24'	20'	11.1	10.7	5.6	
FE	RT	992+69.90	20'	30'	36'	30'		47.8		
FE	LT	992+94.59	20'	30'	16'	30'		33.0		
PE	RT	999+34.39	12'	20'	17'	20'	11.1	7.4	5.6	
PE	RT	1004+91.23	12'	20'	21'	20'	11.1	9.4	5.6	
FE	LT	1005+23.50	20'	30'	35'	30'		51.0		
PE	LT	1010+11.66	14'	20'	67'	20'				159.3
PE	LT	1014+49.61	24'	20'	104'	20'	18.6	92.4	9.4	
FE	RT	1015+50.00	20'	30'	10'	30'		28.5		
PE	RT	1020+40.20	14'	20'	58'	20'	12.3	30.2	6.2	
PE	RT	1024+79.53	12'	20'	118'	20'	11.1	52.4	5.6	
FE	RT	1033+71.19	20'	30'	74'	30'		75.9		
FE	LT	1033+71.19	20'	30'	28'	30'		41.9		
PE	RT	1044+19.62	14'	20'	71'	20'	12.3	36.8	6.2	
FE	LT	1052+00.00	20'	30'	24'	30'		38.9		
FE	LT	1057+73.59	20'	30'	14'	30'		31.5		
PE	RT	1064+85.03	20'	20'	58'	20'	16.1	43.0	8.1	
FE	LT	1064+85.03	20'	30'	7'	30'		26.3		
FE	RT	1069+79.54	20'	30'	48'	30'		56.7		
FE	LT	1076+27.82	20'	30'	13'	30'		30.8		
FE	RT	1082+19.32	20'	30'	49'	30'		57.4		
FE	LT	1082+19.32	20'	30'	13'	30'		30.8		
PE	RT	1084+56.50	13'	20'	58'	20'	11.7	27.7	5.9	
FE	LT	1084+56.50	20'	30'	27'	30'		41.1		
PE	RT	1086+63.29	12'	20'	59'	20'	11.1	26.2	5.6	
PE	RT	1092+40.21	20'	20'	46'	20'	16.1	34.1	8.1	
FE	LT	1094+13.20	20'	30'	12'	30'		30.0		
PE	RT	1096+13.07	30'	20'	36'	20'	22.4	40.0	11.3	
FE	RT	1099+00.00	20'	30'	37'	30'		48.5		
PE	LT	1099+78.51	14'	20'	20'	20'	12.3	10.4	6.2	
PE	LT	1105+82.37	16'	20'	33'	20'	13.6	19.6	6.8	
FE	LT	1108+48.38	20'	30'	49'	30'		57.4		
PE	LT	1113+30.50	12'	20'	43'	20'	11.1	18.9	5.6	
FE	RT	1117+23.30	20'	30'	8'	30'		27.1		
PE	RT	1119+64.18	16'	20'	33'	20'	13.6	19.5	6.8	
PE	LT	1127+96.78	20'	20'	39'	20'	16.1	35.7	8.1	
PE	RT	1129+47.33	12'	20'	11'	20'	11.1	4.7	5.6	
FE	RT	1132+80.91	20'	30'	18'	30'		34.5		
PE	RT	1134+82.16	12'	20'	25'	20'	11.1	11.0	5.6	
FE	LT	1140+15.61	20'	30'	8'	30'		27.1		
FE	RT	1140+67.23	20'	30'		30'		21.1		
TOTALS							309	1477	156	159

SIDE ROAD ENTRANCE SCHEDULE (NEW PAVEMENT)										
PUBLIC ROAD	TYPE	SIDE / STATION	WIDTH	LENGTH		RADI	AGGREGATE BASE COURSE TYPE B	AGGREGATE SURFACE COURSE TYPE B	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	
				u	L <sub>2</sub>		TON	TON	TON	
TWP RD 950E 1725N	FE	RT	9+00.00	20'	30'	30'			36.5	
TWP RD 900E 1550N IOLA RD	PE	LT	11+22.00	12'	20'	10'	20'	15.2	4.4	7.7
	PE	RT	11+58.00	12'	20'	25'	20'	15.2	11.1	7.7
	PE	RT	12+50.00	20'	20'		20'	21.2		10.7
TWP RD 1000E 1500N	PE	LT	11+54.00	56'		11'		19.9		11.0
TOTALS							72	52	37	

PUBLIC ROAD SCHEDULE									
PUBLIC ROAD	SIDE / STATION	WIDTH	LENGTH	TAPER		RADI	BITUMINOUS BASE COURSE SUPERPAVE 8"	BITUMINOUS CONC SURFACE COURSE SUPERPAVE MIX "C", NSO	
				LENGTH	END WIDTH				
				W <sub>1</sub>	L <sub>1</sub>				L <sub>2</sub>
TWP RD 950E 1725N	RT	1006+50.30	20'	135'	50'	12'	30'	418.4	46.9
TWP RD 960E 1700N	LT	1020+41.73	20'	165'	50'	14'	30'	492.0	55.1
TWP RD 975E 1650N	RT	1048+01.46	20'	235'	50'	12'	30'	639.0	71.6
TWP RD 975E 1625N	LT	1063+01.37	20'	185'	50'	12'	30'	529.8	59.3
TWP RD 975E 1600N	RT	1076+49.25	20'	139'	50'	12'	30'	416.4	46.6
TWP RD 990E 1550N IOLA RD	LT	1104+04.37	20'	235'	50'	13'	30'	1091.6	122.3
TWP RD 1000E 1500N	LT	1131+54.81	20'	235'	50'	15'	30'	647.0	72.5
TOTAL							4234	474	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE: 12/14/04

DRAWN BY: JJC  
CHECKED BY: WHG