


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774		EFFINGHAM	344	76

STA. 1007+00.00 TO STA. 1021+00.00
 FED. ROAD DIST. NO. 7 (ILLINOIS) FED. AID PROJECT
 • 107WRS-1, 107BY, 107BY-1 & 107B-2
CONTRACT NO. 94827



PERMANENT SURVEY MARKERS, TYPE 1
 STA. 1016+00.00 1 EACH

TYPE D INLET BOX, STANDARD 609006
 RT STA. 1010+26.80 1 EACH
 RT STA. 1013+19.80 1 EACH
 RT STA. 1017+59.66 1 EACH
 RT STA. 1020+16.30 1 EACH
 TOTAL 4 EACH

REMOVE INLET BOX
 RT STA. 1010+15.85 1 EACH
 RT STA. 1013+09.67 1 EACH
 RT STA. 1017+58.81 1 EACH
 RT STA. 1020+14.91 1 EACH
 TOTAL 4 EACH

PIPE DRAINS, 12"
 RT STA. 1010+26.80 80'
 RT STA. 1013+19.80 60'
 RT STA. 1017+59.66 65'
 RT STA. 1020+16.30 56'
 TOTAL 261'

CONCRETE THRUST BLOCKS
 RT STA. 1010+26.80 1 EACH
 RT STA. 1013+19.80 1 EACH
 RT STA. 1017+59.66 1 EACH
 RT STA. 1020+16.30 1 EACH
 TOTAL 4 EACH

END SECTIONS, 12"
 RT STA. 1010+26.80 1 EACH
 RT STA. 1013+19.80 1 EACH
 RT STA. 1017+59.66 1 EACH
 RT STA. 1020+16.30 1 EACH
 TOTAL 4 EACH

PIPE UNDERDRAIN REMOVAL
 LT STA. 1007+00.00 - STA. 1009+80.00 280'
 RT STA. 1007+00.00 - STA. 1009+98.00 298'
 LT STA. 1013+02.00 - STA. 1017+44.00 422'
 RT STA. 1013+22.00 - STA. 1017+44.00 422'
 LT STA. 1020+32.00 - STA. 1021+00.00 68'
 RT STA. 1020+32.00 - STA. 1021+00.00 68'
 TOTAL 1578'

PIPE UNDERDRAINS FABRIC LINED TRENCH, 6"
 LT STA. 1007+00.00 - STA. 1009+70.00 270'
 RT STA. 1007+00.00 - STA. 1010+08.00 308'
 LT STA. 1012+96.00 - STA. 1016+00.00 304'
 RT STA. 1013+42.00 - STA. 1016+00.00 258'
 LT STA. 1016+00.00 - STA. 1017+36.00 136'
 RT STA. 1016+00.00 - STA. 1017+36.00 136'
 LT STA. 1020+38.00 - STA. 1021+00.00 62'
 RT STA. 1020+38.00 - STA. 1021+00.00 62'
 TOTAL 1536'

