teasleyck
12/17/2004
d:\projects\94941d\d00902pa.dgn

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
752	(106-2Z)TS	FAYETTE		3
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 94941

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE X080-2A		
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	217	217		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19	19		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	185	185		
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	324	324		
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	988	988		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	14	14		
50102400	CONCRETE REMOVAL	CU YD	2.1	2.1		
50300160	NEOPRENE EXPANSION JOINT 4"	FOOT	34	34		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2.1	2.1		
50300530	FLOOR DRAIN EXTENSION	EACH	24	24		
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	48	48		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	250	250		
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1312	1312		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	85	85		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2714	2714		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	367	367		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1464	1464		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	5	5		
* 78100300	REPLACEMENT REFLECTOR	EACH	6	6		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	325	325		
X0320887	POLYMER CONCRETE	CU FT	4.2	4.2		
X0321468	PLUG EXISTING DECK DRAINS	EACH	16	16		
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	6	6		
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	33	33		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	149	149		
Z0002600	BAR SPLICERS	EACH	6	6		
Z0003700	BEARING PAD ADJUSTMENT	EACH	120	120		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	31	31		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	9	9		
Z0032700	KEYWAY REPAIR	FOOT	2115	2115		

* SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY