

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
752	(106-22)TS	FAYETTE		4
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 94941

BRIDGE REPAIR SCHEDULE

STRUCTURE NUMBER	LENGTH	BITUMINOUS CONCRETE SURFACE REMOVAL	BITUMINOUS CONCRETE REMOVAL (DECK)	BITUMINOUS CONCRETE SURFACE REMOVAL, 1/2"	CONCRETE REMOVAL	CONCRETE SUPERSTRUCTURE	REINFORCEMENT BARS, EPOXY COATED	BAR SPLICERS	KEYWAY REPAIR	PLUG EXISTING DECK DRAINS	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	DECK SLAB REPAIR (PARTIAL)	WATERPROOFING MEMBRANE SYSTEM	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX C. N50	NEOPRENE EXPANSION JOINT, 4"	SILICONE JOINT SEALER, 1/2"	POLYMER CONCRETE	BEARING PAD ADJUSTMENT	FLOOR DRAIN EXTENSIONS
	FEET	SQ YD	SQ YD	SQ YD	CU FT	CU FT	POUND	EACH	FEET	EACH	SQ YD	SQ YD	SQ YD	TON	GALLON	TON	FEET	FEET	CU FT	EACH	EACH
026-0059	368.91	525	172	98	1.05	1.05	123.1	6	1110	8	19.4	2.2	656	0.50	9.50	74.5	17	16.5	2.1	60	12
Stage I		463	152	87	1.05	1.05	123.1		1005	8	11.6	7.2	656	0.50	9.50	74.5	17	16.5	2.1	60	12
Stage II																					
TOTAL	368.91	988	324	185	2.1	2.1	250	6	2115	16	31	9	1312	1	19	149	34	33	4.2	120	24

PAVEMENT MARKING SCHEDULE

STRUCTURE NUMBER	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTOR PAVEMENT MARKER, REFLECTOR REMOVAL	SHORT TERM PAVEMENT MARKING	PAINT PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER	REPLACEMENT REFLECTOR
	SQ FT	SQ FT	EACH	FEET	FEET	FEET	EACH	EACH
026-0059								
TOTAL	325	367	6	85	1464	2714	5	6

FORMED CONCRETE REPAIR
LESS THAN OR EQUAL TO 5"

Location	View	Area
Bent #2	South	1.375
Bent #3	East	2
	South	4.75
Bent #4	South	2
Bent #5	West	2.75
Bent #6	West	1
	East	4.5
Pier #10	West	2.5
	East	4.5
East Abutment	West	22.5
	TOTAL	47.9 SQ FT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

QUANTITY SCHEDULES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY