F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* X1-2,44(2,3,4)RS,BSMARTFY04-4
** WILLIAMSON/JOHNSON
CONTRACT NO.: 98758

BRIDGE BILL OF MATERIALS

PAY CODE NO.	XZ193500	X0320887	X0321468	X0321743	X0322933	X0322194	X032256	X0322932	Z0006204	Z0065730
BRIDGE NOS.	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4 IN	POLYMER CONCRETE	PLUG EXISTING DECK DRAINS	SILICONE JOINT SEALER 1 IN	SILICONE JOINT SEALER 2 1/2 IN	POLYMER MODIFIED PORTLAND CEMENT MORTAR	STIFFENER INTERSECTION MODIFICATION	SILICONE JOINT SEALER 1 1/2 IN	BRIDGE DECK HYDRO-SCARIFICATION (1/2 IN)	SLOPE WALL SLURRY PUMPING
	SQ YD	CU FT	EACH	FOOT	FOOT	SQ FT	EACH	FOOT	SQ YD	CU YD
100-0060	1,855.0	11.9	8		127				1,855	4.5
WILLIAMSON CO. TOTAL	1,855.0	11.9	8	0.0	127	0.0	0	0.0	1,855	4.5
044-0029							20			
044-0030							20			
044-0031										
044-0033										
044-0034										
044-0035										
044-0036										
044-0037	463.0	7.9	18	41.5		25.0		41.5	463	3.0
044-0038	463.0	7.9	9	41.5		85.0		41.5	463	1.5
JOHNSON CO TOTAL	926.0	15.8	27	83.0	0.0	110.0	40	83.0	926	4.5
PROJECT TOTAL	2,781.0	27.7	35	83.0	127	110.0	40	83.0	2,781	9.0

BRIDGE BILL OF MATERIALS CON'T

PAY CODE NO.	50102400	50300255	50300260	50300310	50300530	50500405	50500715	50501130	50800205	70100700	70100800
BRIDGE NOS.	CONCRETE REMOVAL *	CONCRETE SUPERSTRUCTURE *	BRIDGE DECK GROOVING	ELASTOMERIC BEARING ASSEMBLY, TYPE I	FLOOR DRAIN EXTENSION	FURNISHING AND ERECTING STRUCTURAL STEEL	JACK AND REMOVE EXISTING BEARINGS	STRUCTURAL STEEL REPAIR	REINFORCEMENT BARS, EPOXY COATED *	TRAFFIC CONTROL AND PROTECTION 701406	TRAFFIC CONTROL AND PROTECTION 701401
	CU YD	CU YD	SQ YD	EACH	EACH	POUND	EACH	POUND	POUND	LSUM	LSUM
100-0060	0.2	0.4	1,764.0	12	4	3,820	12		62	0.1	0.16
WILLIAMSON CO. TOTAL	0.2	0.4	1,764.0	12	4	3,820	12	0	62	0.1	0.16
044-0029	0.2	0.6							106		
044-0030	0.4	0.8							131		
044-0031					16						
044-0033					8			480			
044-0034					21						
044-0035					20						
044-0036					16						
044-0037	0.1	1.0	438.5						128	0.1	0.17
044-0038		0.6	438.5						80	0.1	0.17
JOHNSON CO TOTAL	0.7	3.0	877.0	0	81	0	0	480	445	0.2	0.34
PROJECT TOTAL	** 0.9	3.4	2,641.0	12	85	3,820	12	480	507	0.3	0.50

* WINGWALL MODIFICATION - SEE SAFETY PLAN SHEETS # 127 - 136
** SEE MISCELLANEOUS CONCRETE REMOVAL SCHEDULE FOR PROJECT TOTAL, SHEET # 32

Thursday January 13, 2005 @ 8:37:47 AM
d:\proj\acts\d98758\98758ces3.dgn 1:1=2=18,20=63

SCHEDULE: BRIDGE BILL OF MATERIALS