F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24	*	**	189	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* XI-2.44(2,3,4)RS,BSMARTFY04-4
** WILLIAMSON/JOHNSON
CONTRACT NO.: 98758

EARTHWORK SCHEDULE

LOCATION STA TO STA (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	WORK OFFSET FROM E.P. FOOT	EARTH EXCAVATION CU YD	FOR INFORMATION ONLY: AVERAGE SHRINKAGE FACTOR %	EARTH EXCAVATION (ADJUSTED) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD	BORROW SWELL FACTOR %	BORROW EXCAVATION CU YD	REMARKS
FAI 24									
WILLIAMSON CO.									
EB LANES									
RT 133+55 (MP 1.8)	32	6	N/A	6		6	N/A		
WB LANES									
LT 134+31 (MP 1.8)	48	61	N/A	61		61	N/A		
WILLIAMSON CO. TOTALS		67							
JOHNSON CO.									
EB LANES									
RT 173+97 (MP 2.6)	87	8	N/A	8		8	N/A		MATERIAL TO BE PLACED BEHIND WINGWALLS
RT 176+11 (MP 2.6)	115	22	N/A	22		22	N/A		MATERIAL TO BE PLACED BEHIND WINGWALLS
RT 183+45 (MP 2.7)	75	23	N/A	23		23	N/A		
RT 211+78 (MP 3.3)	112	8	N/A	8		8	N/A		
RT 349+24 (MP 5.9)	100	56	N/A	56		56	N/A		MATERIAL TO BE PLACED BEHIND THE NORTH WINGWALL
RT 356+88 (MP 6.0)	27	35	N/A	35		35	N/A		
RT 194+60 (MP 11.0)	90	2	N/A	2		2	N/A		
RT 231+85 (MP 11.7)	100	35	N/A	35		35	N/A		
RT 238+58 (MP 11.8)	100	8	N/A	8		8	N/A		
RT 250+35 (MP 12.0)	100	12	N/A	12		12	N/A		
RT 255+90 (MP 12.1)	110	12	N/A	12		12	N/A		
RT 270+52 (MP 12.4)	80	6	N/A	6		6	N/A		MATERIAL TO BE PLACED BEHIND THE SOUTH WINGWALL
RT 317+96 (MP 13.3)	125	19	N/A	19		19	N/A		
RT 318+05 (MP 13.3)	125	3	N/A	3		3	N/A		
LT 109+35 TO 112+35 (MP 9.4)	168 TO 190	111	N/A	111		111	N/A		MATERIAL TO BE PLACED LT STA 112+00 TO STA 118+00 (MP 9.5) (WBL
WB LANES									
RT 174+17 (MP 10.6)	120	7	N/A	7		7	N/A		MATERIAL TO BE PLACED BEHIND WINGWALLS
RT 177+08 (MP 10.6)	150	5	N/A	5		5	N/A		
RT 177+19 (MP 10.6)	150	7	N/A	7		7	N/A		
RT 191+94 (MP 10.9)	120	11	N/A	11		11	N/A		MATERIAL TO BE PLACED BEHIND SOUTH WINGWALLS
RT 192+10 (MP 10.9)	120	2	N/A	2		2	N/A		MATERIAL TO BE PLACED BEHIND SOUTH WINGWALLS
LT 174+60 (MP 2.6)	140	37	N/A	37		37	N/A		
LT 182+20 (MP 2.7)	60	7	N/A	7		7	N/A		
LT 182+20 (MP 2.7)	60	6	N/A	6		6	N/A		
LT 180+64 (MP 10.7)	200	67	N/A	67		67	N/A		
LT 273+82 (MP 12.4)	140	4	N/A	4		4	N/A		MATERIAL TO BE PLACED BEHIND THE SOUTH WINGWALL
LT 273+84 (MP 12.4)	140	28	N/A	28		28	N/A		MATERIAL TO BE PLACED BEHIND THE SOUTH WINGWALL
LT 292+77 (MP 12.8)	45	10	N/A	10		10	N/A		
FAS 927 INTERCHANGE									
RAMP A									
0+38 TO 1+25		10	N/A	6	8	-3	25%		RAMP WIDENING
RAMP B									
10+75 TO 11+51		13	N/A	8	4	7	25%		RAMP WIDENING
RAMP C									
0+40 TO 1+25		4	N/A	2	8	-7	25%		RAMP WIDENING
RAMP D									
10+25 TO 11+03		3	N/A	2	5	-4	25%		RAMP WIDENING
JOHNSON CO. TOTALS		581							
PROJECT TOTAL		648							

Tuesday November 16, 2004 8:44:11 PM
C:\pw_work\dot\d0502126\sch\d0502126sch02.dgn LH2-18,28-63