

PIPE UNDERDRAINS, 4"

F.A. - RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	24
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* X1-2,44(2,3,4)RS,BSMARTFY04-4				
** WILLIAMSON/JOHNSON				
CONTRACT NO.: 98758				

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	STONE RIPRAP CLASS A2		COMMENTS
					INFO ONLY LENGTH	PAY ITEM TON	
	FOOT	FOOT	EACH	FOOT	FOOT	TON	
<b>WB LANES RT (MEDIAN SHOULDER)</b>							
118 + 90.43 AH TO 134 + 80 (MP 1.8)	1,590			1,590			CONNECTS TO THE FIRST UNDERDRAIN IN JOHNSON CO.
120 + 00		12	1	5			
125 + 00		12	1	5			
130 + 00		12	1	5			
<b>RAMP CA RT (OUTSIDE SHOULDER)</b>							
6 + 09.57 BK TO 41 + 00 (MP 1.3)	3,490			3,490			STA 25+00 IS A CREST
10 + 00		16	1	9			
15 + 00		16	1	9			
20 + 00		16	1	9			
29 + 00		16	1	9			
33 + 00		16	1	9			
37 + 00		16	1	9			
41 + 00		16	1	9			
<b>WB LANES LT (OUTSIDE SHOULDER)</b>							
118 + 90.43 AH TO 134 + 80 (MP 1.8)	1,590			1,590			CONNECTS TO THE FIRST UNDERDRAIN IN JOHNSON CO.
120 + 00		16	1	9			
125 + 00		16	1	9			
130 + 00		16	1	9			
<b>WILLIAMSON CO. TOTALS</b>							
	25,434	688	49	25,779		39	
<b>JOHNSON CO. EB LANES RT (OUTSIDE SHOULDER)</b>							
134 + 80 TO 148 + 00 (MP 2.0)	1,320			1,320			CONNECTS TO THE LAST UNDERDRAIN IN WILLIAMSON CO.
135 + 08		16	1	9			
140 + 08		16	1	9	85	7	
145 + 08		16	1	9			
148 + 00		14	1	9	60	5	
GAP STRUCTURE # 044 - 0029							
155 + 00 TO 159 + 80 (MP 2.3)	480			480			
155 + 00		16	1	9	60	5	
172 + 25 TO 219 + 00 (MP 3.4)	4,675			4,675			
172 + 25		16	1	9			
177 + 25		16	1	9			
182 + 25		16	1	9			
187 + 25		16	1	9			
192 + 25		16	1	9			
197 + 25		16	1	9			
202 + 25		16	1	9			
207 + 25		16	1	9			
212 + 25		16	1	9			
217 + 25		16	1	9			
228 + 50 TO 271 + 00 (MP 4.4)	4,250			4,250			SAG LOCATION
232 + 50		16	1	9			
236 + 50		16	1	9			
240 + 50		16	1	9			
244 + 35		32	2	9			
248 + 85		16	1	9			
253 + 35		16	1	9			
257 + 85		16	1	9			
262 + 35		16	1	9			
266 + 85		16	1	9			
294 + 00 TO 310 + 00 (MP 5.2)	1,600			1,600			SAG LOCATION
298 + 00		13	1	9	70	6	
302 + 00		13	1	9	160	13	
305 + 50		26	2	9	90	8	
319 + 00 TO 326 + 00 (MP 5.5)	700			700			
319 + 00		16	1	9			
322 + 50		16	1	9			

Tuesday, November 16, 2004 6:25:37 PM  
c:\gto\beta\sta\98758\24.ctb 24.dwg 24.000 1/28/04 11:27:18 AM