F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24	*	**	189	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* X1-2,44(2,3,4)RS,BSMARTFY04-4
** WILLIAMSON/JOHNSON
CONTRACT NO.: 98758

PIPE UNDERDRAINS, 4"

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	STONE RIPRAP CLASS A2 INFO ONLY LENGTH	STONE RIPRAP CLASS A2 PAY ITEM	COMMENTS
	FOOT	FOOT	EACH	FOOT	FOOT	TON	
EB LANES							
RT (OUTSIDE SHOULDER)							
338 + 00 TO 360 + 00 (MP 6.1)	2,200			2,200			
338 + 00		16	1	9			
342 + 50		16	1	9			STA 347+00 IS A CREST
351 + 50		16	1	9			
356 + 00		16	1	9			
360 + 00		16	1	9			
370 + 00 TO 382 + 00 (MP 6.5)	1,200			1,200			
372 + 50		16	1	9			
375 + 00		26	2	9	100	8	SAG LOCATION
378 + 50		16	1	9			
390 + 00 TO 401 + 00 (MP 6.8)	1,100			1,100			
390 + 00		16	1	9			
394 + 00		13	1	9	90	8	
398 + 00		16	1	9			
411 + 38.24 TO 418 + 04.31 (MP 7.2)	666			666			LOCATION: OUTSIDE OF CONNECTING RAMP - SEE TYPICAL SECTION
418 + 04.31 TO 429 + 34.4 BK (MP 7.4)	1,130			1,130			
411 + 38		16	1	9			
415 + 88		16	1	9			
420 + 38		16	1	9			
424 + 88		16	1	9			
441 + 92.74 TO 453 + 78.32 (MP 7.9)	1,186			1,186			LOCATION: OUTSIDE OF CONNECTING RAMP - SEE TYPICAL SECTION
453 + 78.32 TO 495 + 00 (MP 8.7)	4,122			4,122			
446 + 80		16	1	9			
451 + 60		16	1	9			
456 + 40		16	1	9			
461 + 20		16	1	9			
466 + 00		16	1	9			
470 + 80		16	1	9			
475 + 60		16	1	9			
480 + 40		16	1	9	70	6	
485 + 20		16	1	9			
490 + 00		16	1	9	100	8	
495 + 00		16	1	9			
518 + 00 TO 524 + 83.61 BK (MP 9.2)	684			684			
102 + 46.58 AH TO 117 + 00 (MP 9.5)	1,453			1,453			
523 + 00		16	1	9			
105 + 63		16	1	9			
110 + 63		16	1	9			
115 + 00		26	2	9	130	11	SAG LOCATION
137 + 20 TO 156 + 20 (MP 10.2)	1,900			1,900			
137 + 20		16	1	9			
142 + 20		16	1	9			
147 + 20		16	1	9			
152 + 20		16	1	9			
174 + 20 TO 186 + 15 (MP 10.8)	1,195			1,195			
178 + 20		16	1	9			
182 + 20		13	1	9	115	10	
186 + 15		13	1	9	120	10	
GAP STRUCTURE # 044 - 0037							
187 + 35 TO 199 + 00 (MP 11.1)	1,165			1,165			
191 + 20		13	1	9	80	7	
195 + 10		16	1	9	70	6	
199 + 00		16	1	9			
226 + 35 TO 262 + 00 (MP 12.2)	3,565			3,565			
231 + 35		13	1	9	100	8	
236 + 35		13	1	9	50	4	
241 + 35		16	1	9			
246 + 35		16	1	9			
251 + 35		16	1	9			
255 + 00		32	2	9			SAG LOCATION
258 + 50		16	1	9			

Tuesday, November 16, 2004 8:47:46 PM
d:\projects\98758\02102\02102.dgn, V=2-18.29-63

SCHEDULE: PIPE UNDERDRAINS, 4"