F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	27
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

* X1-2,44(2,3,4)RS,BSMARTFY04-4
** WILLIAMSON/JOHNSON
CONTRACT NO.: 98758

PIPE UNDERDRAINS, 4"

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	STONE RIPRAP CLASS A2 INFO ONLY LENGTH	STONE RIPRAP CLASS A2 PAY ITEM	COMMENTS
	FOOT	FOOT	EACH	FOOT	FOOT	TON	
EB LANES							
LT (MEDIAN SHOULDER)							
411 + 38.24 TO 418 + 04.31 (MP 7.2)	666			666			
418 + 04.31 TO 429 + 34.4 BK (MP 7.4)	1,130			1,130			
411 + 38		12	1	5			
415 + 90		12	1	5			
420 + 40		12	1	5			
424 + 90		12	1	5			
441 + 92.74 TO 453 + 78.32 (MP 7.9)	1,186			1,186			
453 + 78.32 TO 495 + 00 (MP 8.7)	4,122			4,122			
446 + 75		12	1	5			
451 + 55		12	1	5			
456 + 35		12	1	5			
461 + 15		12	1	5			
465 + 95		12	1	5			
470 + 75		12	1	5			
475 + 55		12	1	5			
480 + 35		12	1	5			
485 + 15		12	1	5			
490 + 15		12	1	5			
495 + 00		12	1	5			
518 + 00 TO 524 + 83.61 BK (MP 9.2)	684			684			
102 + 46.58 AH TO 117 + 00 (MP 9.5)	1,453			1,453			
523 + 00		12	1	5			
105 + 63		12	1	5			
110 + 63		12	1	5			
115 + 00		24	2	5			SAG LOCATION
137 + 20 TO 156 + 20 (MP 10.2)	1,900			1,900			
137 + 20		12	1	5			
142 + 20		12	1	5			
147 + 20		12	1	5			
152 + 20		12	1	5			
174 + 20 TO 186 + 15 (MP 10.8)	1,195			1,195			
178 + 20		10	1	5			
182 + 20		9	1	5	75	6	
186 + 15		9	1	5	100	8	
GAP STRUCTURE # 044 - 0037							
187 + 35 TO 199 + 00 (MP 11.1)	1,165			1,165			
191 + 20		9	1	5	100	8	
195 + 10		12	1	5	75	6	
199 + 00		12	1	5			
226 + 35 TO 262 + 00 (MP 12.2)	3,565			3,565			
231 + 35		9	1	5	70	6	
236 + 35		9	1	5	100	8	
241 + 35		12	1	5			
246 + 35		12	1	5			
251 + 35		12	1	5			
255 + 00		24	2	5			SAG LOCATION
258 + 50		12	1	5			
268 + 20 TO 277 + 90 (MP 12.5)	970			970			
268 + 20		12	1	5			
273 + 05		12	1	5			
290 + 40 TO 320 + 50 (MP 13.4)	3,010			3,010			
295 + 40		12	1	5			
300 + 40		12	1	5			
305 + 40		12	1	5			
310 + 40		12	1	5			
315 + 40		12	1	5			
320 + 50		12	1	5			

SCHEDULE: PIPE UNDERDRAINS, 4"

Tuesday November 16, 2004 @ 2:47:16 PM
c:\projects\d902102\d902102sc-3.m32 LV=2-18,20-63