

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	29
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* X1-2,44(2,3,4)RS,BSMARTFY04-4				
** WILLIAMSON/JOHNSON				
CONTRACT NO.: 98758				

## PIPE UNDERDRAINS, 4"

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	STONE RIPRAP CLASS A2		COMMENTS
					INFO ONLY	PAY ITEM	
					LENGTH	TON	
<b>WB LANES</b>							
<b>RT (MEDIAN SHOULDER)</b>							
446 + 28.12 TO 495 + 00 (MP 8.7)	4,872			4,872			
451 + 18		12	1	5			
456 + 08		12	1	5			
460 + 98		12	1	5			
465 + 88		12	1	5			
470 + 78		12	1	5			
475 + 68		12	1	5			
480 + 58		12	1	5			
485 + 48		12	1	5			
490 + 38		12	1	5			
495 + 00		12	1	5			
518 + 00 TO 524 + 83.61 BK (MP 9.2)	684			684			
102 + 46.58 AH TO 117 + 00 (MP 9.5)	1,453			1,453			
523 + 00		12	1	5			
105 + 63		12	1	5			
110 + 63		12	1	5			
115 + 50		24	2	5			SAG LOCATION
135 + 20 TO 153 + 85 (MP 10.2)	1,865			1,865			
135 + 20		12	1	5			
140 + 20		12	1	5			
145 + 20		12	1	5			
150 + 20		12	1	5			
172 + 20 TO 187 + 05.29 (MP 10.8)	1,485			1,485			
177 + 20		12	1	5			
182 + 20		12	1	5			
187 + 00		12	1	5			
GAP STRUCTURE # 044 - 0038							
188 + 16.72 TO 199 + 00 (MP 11.1)	1,083			1,083			
193 + 50		9	1	5	100	8	
199 + 00		12	1	5			
228 + 00 TO 264 + 00 (MP 12.3)	3,600			3,600			
233 + 00		9	1	5	80	7	
238 + 00		9	1	5	100	8	
243 + 00		12	1	5	75	6	
248 + 00		12	1	5			
253 + 00		12	1	5			
258 + 00		24	2	5			
261 + 00		12	1	5			SAG LOCATION
269 + 00 TO 278 + 80 (MP 12.6)	980			980			
269 + 00		12	1	5			
274 + 00		12	1	5			
290 + 40 TO 296 + 50 (MP 12.9)	610			610			
293 + 45		12	1	5			
296 + 50		12	1	5			
308 + 00 TO 320 + 50 (MP 13.4)	1,250			1,250			
312 + 00		12	1	5			
316 + 00		12	1	5			
320 + 50		12	1	5			
<b>LT (OUTSIDE SHOULDER)</b>							
134 + 80 TO 148 + 00 (MP 2.0)	1,320			1,320			CONNECTS TO THE LAST UNDERDRAIN IN WILLIAMSON CO.
135 + 00		16	1	9			
140 + 00		16	1	9			
145 + 00		13	1	9	60	5	
148 + 00		13	1	9	45	4	
GAP STRUCTURE # 044 - 0030							
155 + 50 TO 158 + 10 (MP 2.3)	260			260			
155 + 50		14	1	9	60	5	

Tuesday, November 16, 2004 @ 2:47:05 PM  
 c:\p\electa\982102\982102\sec3.mxd L:\2-18-20-03