

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24	*	**	189	54
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* X1-2,41(2,3,4)RS,BSMARTFY04-4
 ** WILLIAMSON/JOHNSON
 CONTRACT NO.: 98758

TREE REMOVAL

LOCATION STA TO STA (MP IS THE LAST STA. UNLESS OTHERWISE NOTED)	OFFSET FROM E.P. FEET	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL ACRES	REMARKS
		UNIT	UNIT	ACRE	
WB LANES					
LT 302+50 (MP 5.0)	180	6			6' UP THE FORESLOPE
LT 302+70 (MP 5.0)	202	11			1' UP THE BACKSLOPE
LT 302+75 (MP 5.0)	205	9			4' UP THE FORESLOPE
LT 302+88 (MP 5.0)	203	6			2' UP THE BACKSLOPE
LT 303+40 (MP 5.0)	166		18		DIRECTLY BEHIND AND IN THE MIDDLE OF NORTH WING-TREAT STUMP WITH HERBICIDE
LT 304+10 (MP 5.0)	160	11			1' UP THE BACKSLOPE
LT 320+17 (MP 5.3)	38	10			REMOVE TREE @ BEGINNING OF PAVED DITCH (UP THE BACKSLOPE)
LT 321+00 (MP 5.4)	48	9			SOUTH OF PAVED DITCH AND 24' UP FROM THE DITCH (OAK)
LT 1354+40 (MP 6.0)	90	7 10			TREES EAST OF CULVERT (WILLOW), COST TO INCLUDE REMOVAL OF 7 SMALLER TREES AND BRUSH
LT 1354+60 (MP 6.0)	90	8 8 8 8			TREES EAST OF CULVERT (WILLOW), COST TO INCLUDE REMOVAL SMALLER TREES WITHIN DITCH FLOW LINE
LT 1391+32 TO 1392+35 (MP 6.7)	55 TO 130			0.7	
LT 1392+07 (MP 6.7)	126	7			1' UP THE BACKSLOPE
LT 1392+08 (MP 6.7)	131	7			6' UP THE BACKSLOPE
LT 1415+50 (MP 7.1)	144	7			10' PAST HEADWALL (WILLOW)
LT 1415+50 (MP 7.1)	124	8			BEHIND END OF SOUTH WING-TREAT STUMP WITH HERBICIDE
LT 453+10 (MP 7.8)	116	6 6 6 6 7			BUNDLE OF TREES 5' PAST HEADWALL, COST TO INCLUDE ANY LESS THAN 6"
LT 453+10 (MP 7.8)	116	8			BUNDLE OF TREES 5' PAST HEADWALL, COST TO INCLUDE ANY LESS THAN 6"
LT 458+79 (MP 7.9)	65 TO 100			0.01	SEE PLAN FOR REMOVAL CENTERED ON CULVERT, SKEWED AHEAD
LT 462+00 (MP 8.0)	150	8			CENTERED DIRECTLY BEHIND WEST WING-TREAT STUMP WITH HERBICIDE
LT 486+30 (MP 8.5)	123	6			
LT 486+30 (MP 8.5)	124	6			
LT 486+32 (MP 8.5)	111	6			
LT 486+32 (MP 8.5)	119	7			
LT 486+35 (MP 8.5)	118	6			
LT 486+41 (MP 8.5)	120	6			
LT 486+41 (MP 8.5)	123	6			
LT 486+45 (MP 8.5)	120	6			(CEDAR)
LT 486+45 (MP 8.5)	123	7			(CEDAR)
LT 486+48 (MP 8.5)	176	6			SOUTH OF CONNECTING PAVED DITCH 15' FROM END, (CEDAR)
LT 486+51 (MP 8.5)	117	7			(CEDAR)
LT 486+54 (MP 8.5)	124	6			25' UPSLOPE CENTERED ON CULVERT (CEDAR)
LT 486+54 (MP 8.5)	114	7			(CEDAR)
LT 486+57 (MP 8.5)	23	7			(CEDAR)
LT 486+67 (MP 8.5)	28	7			(CEDAR)
LT 486+71 (MP 8.5)	30	7			(CEDAR)
LT 486+80 (MP 8.5)	170	9			LEFT OF PAVED DITCH @ THE JUNCTION (CEDAR)
LT 486+85 (MP 8.5)	164	6			RIGHT OF PAVED DITCH, UP FORESLOPE, (WILLOW)
LT 486+98 (MP 8.5)	180	9			LEFT OF PAVED DITCH, UP BACKSLOPE, (CEDAR)
LT 487+06 (MP 8.5)	188	6			LEFT OF CONNECTING PAVED DITCH, UP BACKSLOPE
LT 524+25 (MP 9.2)	67	10			
LT 112+60 (MP 9.4)	164	8			3' ON THE FORESLOPE SIDE
LT 104+80 (MP 9.3)	50 TO 110			0.03	SEE PLAN FOR REMOVAL DOWN SLOPE
LT 112+40 (MP 9.4)	164	8			15' BACK FROM HEADWALL AND SOUTH WING (CEDAR)
LT 116+00 (MP 9.5)	46	6			
LT 138+40 (MP 9.9)	138	8 12			2 TREES, 10' EAST OF SOUTH END OF HEADWALL
LT 148+39 (MP 10.1)	82	8			NORTH SIDE, (PERSIMMON)
LT 148+39 (MP 10.1)	65	7			SOUTH SIDE, (CEDAR)
LT 180+20 (MP 10.7)	220	7 11			2 TREES, (WILLOW)
LT 180+20 (MP 10.7)	240	11			(WILLOW)
LT 180+64 (MP 10.7)	150 TO 200			0.03	SEE PLAN FOR REMOVAL CENTERED ON CULVERT
LT 192+00 (MP 10.9)	10 TO 90			0.04	SEE PLAN FOR REMOVAL BETWEEN S.P.B.G.R. AND PAVED DITCH
LT 193+59 (MP 10.9)	10 TO 130			0.10	SEE PLAN FOR REMOVAL CENTERED ON CULVERT SKEWED AHEAD
LT 188+91 (MP 10.9)	98	6			6' UP THE FORESLOPE (CEDAR)
LT 188+92 (MP 10.9)	108	7			2' UP THE BACKSLOPE (CEDAR)
LT 189+39 (MP 10.9)	98	6			6' UP THE FORESLOPE (CEDAR)
LT 190+03 (MP 10.9)	112	7			2' UP THE BACKSLOPE (CEDAR)
LT 190+28 (MP 10.9)	120	7			6' UP THE BACKSLOPE (CEDAR)
LT 191+08 (MP 10.9)	106	6			4' UP THE FORESLOPE (CEDAR)
LT 191+82 (MP 10.9)	134	6			5' UP THE BACKSLOPE (CEDAR)
LT 192+31 (MP 10.9)	134	9			1' UP THE BACKSLOPE

Monday, December 20, 2004 4:49:08 PM
 c:\paw\ac\11\192102\192102.dwg L:\2-18-20-03