

F.A. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24	*	**	189	55
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* X1-2,44(2,3,4)RS,BSMARTFY04-4				
** WILLIAMSON/JOHNSON				
CONTRACT NO.: 98758				

TREE REMOVAL

LOCATION STA TO STA (MP IS THE LAST STA. UNLESS OTHERWISE NOTED)	OFFSET FROM E.P. FEET	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL ACRES	REMARKS	
		UNIT	UNIT	ACRE		
WB LANES						
LT 194+00	(MP 11.0)	175	6 12			
LT 239+56	(MP 11.8)	10 TO 150		0.11	REMOVE TREES JUST WEST OF COUNTY CROSS-ROAD CULVERT OUTLET	
LT 241+63	(MP 11.8)	30 TO 110		0.09	SEE PLAN FOR REMOVAL FROM S.P.B.G.R. TO DITCH	
LT 241+60	(MP 11.9)	128			SEE PLAN FOR REMOVAL CENTERED ON CULVERT	
LT 241+70	(MP 11.9)	124			8" TREE DSFL OF CULVERT TO BE INCLUDED IN THE COST OF TREE REMOVAL, ACRE, LT STA 241+63	
LT 241+74	(MP 11.9)	127			11" TREE REMOVAL TO BE INCLUDED IN THE COST OF TREE REMOVAL, ACRE, LT STA 241+63, -TREAT STUMP	
LT 244+84	(MP 11.9)	95	6 7		6" TREE DSFL OF CULVERT TO BE INCLUDED IN THE COST OF TREE REMOVAL, ACRE, LT STA 241+63	
LT 244+90	(MP 11.9)	77	8		2 TREES, (CEDAR)	
LT 244+92	(MP 11.9)	82	8		(CEDAR)	
LT 244+96	(MP 11.9)	77	6		(CEDAR), COST TO INCLUDE 3", & 4" TREE REMOVAL, 77' LT STA 244+96	
LT 245+00	(MP 11.9)	81	7		(CEDAR)	
LT 251+64	(MP 12.0)	168 TO 222		0.13	SEE PLAN FOR REMOVAL CENTERED ON CULVERT 85' ABOVE THE HEADWALL SKEWED AHEAD	
LT 253+70	(MP 12.1)	75 TO 134		0.02	SEE PLAN FOR REMOVAL CENTERED ON CULVERT SKEWED BACK	
LT 273+92	(MP 12.5)	150	15		RIGHT OF PAVED DITCH, UP FORESLOPE, (SYCAMORE)	
LT 273+93	(MP 12.5)	130	6 6 7		3 TREES, NORTH SIDE OF WINGWALL, -TREAT STUMPS WITH HERBICIDE, (WILLOW)	
LT 309+13	(MP 13.1)	80		22	LEFT OF PAVED DITCH, UP BACKSLOPE	
LT 312+05	(MP 13.2)	76 TO 132		0.05	SEE PLAN FOR REMOVAL CENTERED ON DITCH	
LT 319+31	(MP 13.3)	144	9		5' OUTSIDE OF CULVERT	
LT 319+31	(MP 13.3)	129	6 8		2 TREES, NORTH WING-TREAT STUMP WITH HERBICIDE	
RT 171+50	(MP 10.5)	38	7		RIGHT OF PAVED DITCH, UP BACKSLOPE, (CEDAR)	
RT 172+42	(MP 10.5)	74	6		RIGHT OF PAVED DITCH, UP BACKSLOPE	
RT 173+50	(MP 10.6)	114	6		RIGHT OF PAVED DITCH, UP BACKSLOPE, (CEDAR)	
RT 173+58	(MP 10.6)	116	7		RIGHT OF PAVED DITCH, UP BACKSLOPE, (CEDAR)	
RT 173+81	(MP 10.6)	124	7		RIGHT OF PAVED DITCH, UP BACKSLOPE	
RT 173+93	(MP 10.6)	130	7		1' RIGHT OF PAVED DITCH, UP BACKSLOPE	
RT 190+75	(MP 10.9)	10 TO 134		0.09	SEE PLAN FOR REMOVAL CENTERED ON PAVED DITCH	
RT 192+00	(MP 10.9)	68 TO 130		0.03	SEE PLAN FOR REMOVAL CENTERED ON CULVERT SKEWED BACK	
RT 193+25	(MP 10.9)	10 TO 130		0.08	SEE PLAN FOR REMOVAL CENTERED ON CULVERT	
RT 237+85	(MP 11.8)	75	7		FORESLOPE	
RT 237+85	(MP 11.8)	100	7		FORESLOPE	
RT 241+43	(MP 11.9)	43	11		FORESLOPE	
JOHNSON CO TOTAL			1922	182	2.30	
JOHNSON COUNTY PAY						
TR 43						
(WB LANES FAI 24)						
LT 1374+00	(MP 6.4)	196 TO 240		0.05	PAID BY COUNTY; SEE PLAN FOR REMOVAL 24' TO 72' LT TR 43 CENTERED ON CULVERT	
JOHNSON CO PAY TOTAL					0.05	
PROJECT TOTAL			2008	200	2.40	

Monday, December 20, 2004 @ 14:55 PM
 C:\p25\mca\1\902102\1\902102.dwg L:\p2-18-20-03