

RIPRAP

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	62
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	
* X1-2,44(2,3,4)RS,BSMARTFY04-4				
** WILLIAMSON/JOHNSON				
CONTRACT NO.: 98758				

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	STONE RIPRAP DITCH	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A5	STONE RIPRAP CLASS A3	STONE RIPRAP CLASS A4	PAY ITEM	GABIONS				FILTER FABRIC FOR USE WITH RIPRAP (SEE NOTE 2)	RIPRAP SLURRY	REMARKS
								INFORMATION ONLY (SEE NOTE 1)						
								AVERAGE						
TON	SQ YD	TON	TON	TON	TON	CU YD	LENGTH FT	WIDTH FT	HEIGHT FT	EST. NO. OF CELLS	SQ YD	SQ YD		
FAI 24														
WILLIAMSON CO.														
F. A. I. 24 / I-57 INTERCHANGE														
RAMP AC														
LT 20+72 TO 26+80 (MP 0.4)	365													RAMP AC
LT 26+80 TO 27+20					22									RAMP AC
LT 57+00					4									RAMP AC
RAMP BC														
RT 7+07 TO 8+67	74											148.0		RAMP BC
RAMP CA														
RT 47+74					4									RAMP CA
RAMP CB														
RT 7+82 TO 12+50	252													RAMP CB
RT 9+10 TO 11+97					161									RAMP CB
RT 23+07 TO 25+46	236													RAMP CB
WILLIAMSON CO. TOTALS														
	927	0	0	0	191	0	0					0	148	
EB LANES														
RT 114+50 TO 115+40 (MP 1.5)	51													
RT 115+89 TO 116+17 (MP 1.5)	17													
RT 124+81 TO 125+57 (MP 1.7)	41													
JOHNSON CO.														
EB LANES														
RT 145+82 TO 147+82 (MP 2.1)	128													
RT 156+80 TO 159+20 (MP 2.3)	187												373.0	
RT 169+01 TO 169+21 (MP 2.5)					6									
RT 169+08 (MP 2.5)					7							4.7	4.7	
RT 172+17 (MP 2.5)					4									
RT 172+17 (MP 2.5)	31													
RT 187+78 (MP 2.8)					5									
RT 195+61 (MP 3.0)	28													
RT 195+61 (MP 3.0)						139								
RT 201+44 TO 202+44 (MP 3.1)					56									
RT 203+65 TO 204+15 (MP 3.2)	31													
RT 211+90 (MP 3.3)					39							77.8		
RT 211+93 TO 213+55 (MP 3.3)	100													
RT 247+07 TO 248+72 (MP 4.0)	108													
RT 264+77 TO 265+85 (MP 4.3)	70													
RT 273+24 (MP 4.5)					67									
RT 273+24 (MP 4.5)	31													
RT 295+86 (MP 4.9)							18	27	6	3	18	77.8		DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
RT 298+00 (MP 4.9)					39									
RT 303+00 (MP 5.0)					97							194.4		
RT 305+66 (MP 5.1)					69							139.0		
RT 307+00 (MP 5.1)					55							110.0		
RT 294+50 TO 308+50 (MP 5.1)					282									BEHIND CONCRETE CURB
RT 313+82 TO 314+48 (MP 5.2)	64													
RT 322+80 TO 325+92 (MP 5.5)	172													
RT 343+40 (MP 5.8)					28							55.6	55.6	RIPRAP SLURRY
RT 365+70 (MP 6.2)			89											
RT 371+94 TO 373+54 (MP 6.4)	101													
RT 374+00 TO 375+50 (MP 6.4)					18									BEHIND CONCRETE CURB
RT 392+00 (MP 6.7)					10									
RT 392+50 (MP 6.7)												89.0	100.0	

Monday, December 20, 2014 8:20:42 PM
C:\projects\102102\102102.mxd L:\1-18-2014-53