

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24	*	**	189	64
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* X1-2,44(2,3,4)RS,BSMARTFY04-4
 ** WILLIAMSON/JOHNSON
 CONTRACT NO.: 98758

RIPRAP

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	STONE RIPRAP DITCH	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A5	STONE RIPRAP CLASS A3	STONE RIPRAP CLASS A4	PAY ITEM	GABIONS				FILTER FABRIC FOR USE WITH RIPRAP (SEE NOTE 2)	RIPRAP SLURRY	REMARKS
								INFORMATION ONLY (SEE NOTE 1)						
								AVERAGE						
TON	SQ YD	TON	TON	TON	TON	CU YD	LENGTH FT	WIDTH FT	HEIGHT FT	EST. NO. OF CELLS	SQ YD	SQ YD		
EB LANES														
LT 191+50					61							122.2		
LT 192+12							3	3	9	3	3			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
LT 187+46 TO 197+02					193									BEHIND CONCRETE CURB
LT 194+00					58							116.7		
LT 196+96					58							117.0	117.0	RIPRAP SLURRY
LT 230+00					75									
LT 231+72							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
LT 233+00					64							128.0		
LT 233+00	6													
LT 235+97					63							125.0		
LT 235+98														
LT 225+78 TO 238+65	739													
LT 237+40							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
LT 238+00							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
LT 239+00					59							117.3		
LT 239+50 TO 240+00					44									
LT 230+50 TO 242+00					222									BEHIND CONCRETE CURB
LT 241+86					51							102.2		
WB LANES														
LT 141+15 TO 143+96	161													
LT 144+00							8	12	22	1				SEE SCOUR REPAIR DETAIL SHEET 161
LT 142+20 TO 147+80					99									BEHIND CONCRETE CURB
LT 147+55					30							60.0		
LT 150+50 TO 150+60					17									
LT 150+50 TO 157+86	424													
LT 157+00	11													
LT 174+60		56												ENERGY DISSIPATOR
LT 179+07 TO 179+42													35.6	RIPRAP SLURRY EXIST. RIPRAP ALONG PAVED DITCH
LT 181+98 TO 182+17													27.8	RIPRAP SLURRY EXIST. RIPRAP ALONG PAVED DITCH
LT 183+99 TO 184+15												17.8	17.8	RIPRAP SLURRY
LT 187+47					8									
LT 187+47	39													
LT 193+04	25													
LT 193+04						33								
LT 193+04						22								
LT 201+68 TO 202+86	67													
LT 240+01 TO 240+26					14							27.8	27.8	RIPRAP SLURRY
LT 245+83							26							SEE DETAIL SHEET 162
LT 254+85 TO 256+16	93													
LT 295+96 TO 303+05	411													
LT 303+37							164							SEE DETAIL SHEET 163
LT 303+37					52									13' X 6' X 6' BEHIND BOTH WING WALLS
LT 304+47	11													
LT 304+56					47							94.4		
LT 299+50 TO 304+74					97									BEHIND CONCRETE CURB
LT 304+56														
LT 303+64 TO 308+10	256													
LT 320+10	21													
LT 324+83 TO 325+08					14									
LT 331+20	22													
LT 1349+09 TO 1350+99	119													
LT 1370+65 TO 1373+30	164													
LT 1389+80 TO 1393+00					44									BEHIND CONCRETE CURB
LT 1390+00					53									
LT 1391+89							200					105.7		SEE DETAIL SHEET 165 - 166
LT 1391+89												46.7		NORTHWEST WINGWALL - SEE DETAIL SHEET 165
LT 1391+89												12.2		SOUTHEAST WINGWALL - SEE DETAIL SHEET 166
LT 1392+12 TO 1394+00	104													

Monday, December 20, 2004 8:20:42 PM
 c:\paw\mca\19921021\98758\3\32 LV2-18-28-63