

SCHEDULE OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	5-01 5S092 1074 R213.03	5-02 5C092 1074 R214.21	5-03 5C092 1074 L214.50	5-04 5C092 1074 R215.65	5-05 5C092 1074 R022.24	5-06 Grnd Mnt S. leg Lynch Rd. & I-74
VERMILION COUNTY - I-74									
63200310	GUARDRAIL REMOVAL	FOOT	116.00	-	-	-	-	116.00	-
67100100	MOBILIZATION	L SUM	1.00	0.20	0.20	0.20	0.20	0.10	0.10
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3.00	-	1.00	1.00	1.00	-	-
72000300	SIGN PANEL - TYPE 3	SQFT	1140.50	358.50	161.50	145.00	178.50	148.50	148.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	841.50	287.00	118.00	116.00	161.25	159.25	-
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2666.00	-	-	-	-	1196.00	1470.00
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	70.00	70.00	-	-	-	-	-
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	84.00	-	28.00	28.00	28.00	-	-
73400100	CONCRETE FOUNDATIONS	CUYD	6.70	-	-	-	-	2.82	3.80
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	48.50	21.50	9.00	9.00	9.00	-	-
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00	1.00	-	-	-	-	-
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	4.00	-	1.00	1.00	1.00	1.00	-
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	6.00	2.00	1.00	1.00	1.00	1.00	-
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00	2.00	-	-	-	-	-
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GRND, (XLP-TYPE USE), 1" DIA. POLY	FOOT	240.00	-	-	-	240.00	-	-
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.00	0.50	-	-	0.50	-	-
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1.00	-	0.50	0.50	-	-	-
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.00	-	-	-	-	1.00	-
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	43.00	14.00	5.00	5.00	14.00	5.00	-
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	40.00	40.00	-	-	-	-	-
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	72.00	-	24.00	24.00	24.00	-	-
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	4.00	-	1.00	1.00	1.00	1.00	-

*D-5 OVD SIN STR REPL 2011-17

FILE NAME =	USER NAME = bucklesjj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE. 74	SECTION *	COUNTY VERMILION	TOTAL SHEETS 39	SHEET NO. 3
ct:\pwork\pmsdot\bucklesjj\d0241273\056140-sht-Schedule.dgn	PLOT SCALE = 48.0000' / IN.	DRAWN -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 46140				
PLOT DATE = 10/28/2010	DATE -	CHECKED -	REVISED -	ILLINOIS FED. AID PROJECT						