

SCHEDULE OF QUANTITIES INDIVIDUAL TRUSS LOCATIONS

Location No.	5-01			
Structure No.	5 S 092 I074 R213.03			
County / Route	VERMILION CO. - I-74 EB - 0.5 mi. West of G-Street in Tilton			
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
72000300	SIGN PANEL - TYPE 3	SQFT	358.50	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	287.00	
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	70.00	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	21.50	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00	
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00	
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00	
X7012615	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	1.00	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.00	
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	40.00	
There is no electrical service or lighting at this sign structure.				
Pay Item for Changeable Message Signs is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Std.				

Location No.	5-02			
Structure No.	5 C 092 I074 R214.21			
County / Route	VERMILION CO. - I-74 EB - at Exit Ramp for IL 1 Southbound			
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	161.50	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	118.00	
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	28.00	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00	
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00	
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00	
X7012617	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	EACH	1.00	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	5.00	
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	24.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	

Location No.	5-03			
Structure No.	5 C 092 I074 L214.50			
County / Route	VERMILION CO. - I-74 WB - at Exit Ramp for IL 1 Northbound			
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	145.00	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	116.00	
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	28.00	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00	
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00	
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00	
X7012617	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	EACH	1.00	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	5.00	
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	24.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	

Location No.	5-04			
Structure No.	5 C 092 I074 R215.65			
County / Route	VERMILION CO. - I-74 EB - at Bowman Ave / Perrysville Rd			
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	178.50	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	161.25	
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	28.00	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00	
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00	
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00	
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GRND, (XLP-TYPE USE), 1" DIA. POLY	FOOT	240.00	
X7012615	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	1.00	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.00	
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	24.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	
Pay Item for Changeable Message Signs is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Std.				

*D-5 OVD SIN STR REPL 2011-17

FILE NAME =	USER NAME = buckles_jj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES INDIVIDUAL TRUSS LOCATIONS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\pwwork\backles_jj\d0241273\05	0140-sht-Schedule.dgn	DRAWN -	REVISED -			74		VERMILION	39	4
	PLOT SCALE = 1/8" = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:					
	PLOT DATE = 10/28/2010	DATE -	REVISED -		SHEET NO. OF SHEETS STA. TO STA.					
										CONTRACT NO. 46140 ILLINOIS FED. AID PROJECT