* SPECIALTY ITEM

URBAN

| | SUMMARY OF QUANTITIES | | | CONSTRUCTION CODE | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL | 0003 | 0008 | 0021 | | | | | | | | | | | | | | | | | | 0031 | 0040 | | 0043 |
| | | | | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 |
| * | 81400100 | HANDHOLE | EACH | 93 | | | 5 | 7 | 5 | 5 | 8 | 4 | 4 | 5 | 4 | 4 | 4 | 3 | 6 | | 7 | 5 | 8 | 9 | | | | | |
| * | 81400200 | HEAVY-DUTY HANDHOLE | EACH | 31 | | | 1 | 4 | 2 | 2 | 4 | 4 | 2 | 4 | 2 | 2 | 3 | | | | | 1 | | | | | | | |
| * | 81400300 | DOUBLE HANDHOLE | EACH | 29 | | | 1 | 3 | 2 | 1 | 4 | 2 | 2 | 3 | 2 | 2 | 2 | 3 | | | 1 | 1 | | | | | | | |
| * | 81603090 | UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE | FOOT | 18,016 | | | | | | | | | | | | | | | | | | | | | 18,016 | | | | |
| * | 81603115 | UNIT DUCT, 600V, 3-1C NO.1, 1/C NO.1 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE | FOOT | 2,373 | | | | | | | | | | | | | | | | | | | | | 2,373 | | | | |
| * | 81800290 | AERIAL CABLE, 3-1/C NO. 1/0 WITH MESSENGER WIRE | FOOT | 2,626 | | | | | | | | | | | | | | | | | | | | | 2,626 | | | | |
| * | 81800415 | AERIAL CABLE, 4-1/C NO. 6 WITH MESSENGER WIRE | FOOT | 2,395 | | | | | | | | | | | | | | | | | | | | | 2,395 | | | | |
| * | 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 39,866 | | | 663 | 804 | 581 | 740 | 1073 | 621 | 988 | 928 | 645 | 660 | 427 | 355 | 816 | | 540 | 584 | 6249 | 7445 | 15747 | | | | |
| * | 82102250 | LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT | EACH | 4 | | | | | | | | | | | | | | | | | | | | | 4 | | | | |
| * | 82102400 | LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT | EACH | 141 | | | | | | | | | | | | | | | | | | | | | 141 | | | | |
| * | 83050810 | LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM | EACH | 89 | | | | | | | | | | | | | | | | | | | | | 89 | | | | |
| * | 83057350 | LIGHT POLE, WOOD, 60 FOOT, CLASS 4 | EACH | 5 | | | | | | | | | | | | | | | | | | | | | 5 | | | | |
| * | 83057355 | LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM | EACH | 32 | | | | | | | | | | | | | | | | | | | | | 32 | | | | |
| * | 83600200 | LIGHT POLE FOUNDATION, 24" DIAMETER | FOOT | 930 | | | | | | | | | | | | | | | | | | | | | 930 | | | | |
| * | 83800105 | BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE | EACH | 4 | | | | | | | | | | | | | | | | | | | | | 4 | | | | |
| * | 83800205 | BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE | EACH | 89 | | | | | | | | | | | | | | | | | | | | | 89 | | | | |
| * | 84100110 | REMOVAL OF TEMPORARY LIGHTING UNIT | EACH | 41 | | | | | | | | | | | | | | | | | | | | | 41 | | | | |
| * | 84200500 | REMOVAL OF LIGHTING UNIT, SALVAGE | EACH | 42 | | | | | | | | | | | | | | | | | | | | | 42 | | | | |
| * | 85000100 | MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION | WEEK | 1 | | | | | | | | | | | | | | | | | | 1 | | | | | | | |
| * | 85700205 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL | EACH | 12 | | | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | | | | | 1 | | | | | | | |
| * | 85700305 | FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL | EACH | 2 | | | | | | | | | | | | | | 1 | | | 1 | | | | | | | | |
| * | 86000105 | MASTER CONTROLLER (SPECIAL) | EACH | 2 | | | | | | | | | | | | | | | | | | | 1 | 1 | | | | | |
| * | 86400100 | TRANSCEIVER-FIBER OPTIC | EACH | 14 | | | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | | | 1 | 1 | | | | | | | |
| * | 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 16,183 | | | | 2516 | 1232 | 452 | 2816 | 1402 | 1493 | 1753 | 1493 | 1480 | 1546 | | | | | | | | | | | | |
| * | 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 30,132 | | | 280 | 4437 | 1769 | 1051 | 4746 | 1804 | 1948 | 2938 | 1865 | 1879 | 1965 | 884 | 299 | 1772 | 1080 | 1415 | | | | | | | |
| * | 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 33,304 | | | 1561 | 4335 | 1078 | 2022 | 3788 | 1333 | 2215 | 3161 | 1783 | 1788 | 1172 | 1966 | 2782 | | 2180 | 2140 | | | | | | | |