* SPECIALTY ITEM

	SUMMARY OF QUANTITIES			CONSTRUCTION CODE																									
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL	0003	0008	0021																			0031	0040		0043
				1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	19,782			440	2291	1445	801	2431	1675	879	1955	1766	1750	2176	1922				251							
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	42,232			905	8666	1585	1495	8347	2394	2296	5699	1797	1954	1729	1377	1483		849	1656							
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	1,499			150	39	115	92	220	93	398	83	51	76	28	29			31	94							
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	4				2			2																		
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	12									1						4		5	2							
* 87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	1																		1							
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	26			1		2	2	2	3	1	3	3	4	4	1											
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2															1		1								
* 87700160	STEEL MAST ARM ASSEMBLEY AND POLE, 24 FT.	EACH	1																	1								
* 87700180	STEEL MAST ARM ASSEMBLEY AND POLE, 28 FT.	EACH	2			1		1																				
* 87700190	STEEL MAST ARM ASSEMBLEY AND POLE, 30 FT.	EACH	1																	1								
* 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	3					1	1												1							
* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1			1																						
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38FT.	EACH	5			1		1			1	1									1							
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	3						1			1						1										
* 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	5								1			1	1	1		1										
* 87700260	STEEL MAST ARM ASSEMBLEY AND POLE, 44 FT.	EACH	2									1			1													
* 87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1											1														
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	4					1			1				2													
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1											1														
* 87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	2										1			1												
* 87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	2									1		1														
* 87700330	STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH	5						1				2			2												
* 87700340	STEEL MAST ARM ASSEMBLY AND POLE, 58 FT.	EACH	1														1											
* 87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	3								1						2											
* 87700408	STEEL MAST ARM ASSEMBLY AND POLE, 64 FT.	EACH	1										1															
* 87700428	STEEL MAST ARM ASSEMBLY AND POLE, 74 FT.	EACH	1														1											
* 87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	2				1			1																		