* SPECIALTY ITEM

	SUMMARY OF QUANTITIES			CONSTRUCTION CODE																								
			URBAN																									
	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL	0003	0008	0021																	0031	0040		0043
					1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
*	87300925	ELECTRIC CABLE IN CONDUIT , TRACER, NO. 14 1C	FOOT	23,904																			12125	11779					
	X0323005	AUXILIARY VALVE AND VALVE BOX	EACH	9																									9
	X0323160	VIDEO INSPECTION OF STORM SEWER	FOOT	7,344	7,344																								
*	88600700	PREFORMED DETECTOR LOOP	FOOT	12,723			472	1331	667	685	1233	1224	1101	1195	1228	1192	1719	113	117		446								
*	X0323792	LIGHTING CONTROLLER, SINGLE DOOR, CONSOLE TYPE	EACH	2																					2				
	X0323840	WATER MAIN LINE STOP 6"	EACH	4																									4
	X0323841	WATER MAIN LINE STOP 8"	EACH	4																									4
	X0323842	WATER MAIN LINE STOP 12"	EACH	14																									14
*	Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	104																					104				
	X0325012	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 10"	EACH	1																									1
*	X0325134	WIRELESS INTERCONNECT (COMPLETE)	EACH	3																			2	1					
	X0325318	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU YD	2,361	2,361																								
	X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	7,408	7,408																								
	X0325598	DRAINAGE SCUPPERS, DS-12M10	EACH	14		14																							
*	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	15																			8	7					
	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	14			1	1		1	1	1	1	1	1	1	1	1	1		1	1							
	X0325846	ABANDONMENT OF EXISTING WATER MAINS	LSUM	1																									1
	X0325885	STEEL CASING PIPE AUGERED AND JACKED 36"	FOOT	160																									160
*	88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4				2			2																		
	XX008401	BOX CULVERT REMOVAL	FOOT	526	526																								
	Z0062456	TEMPORARY PAVEMENT	SQ YD	53,453	53,453																								
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	84	84																								
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	70	70																								
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	23	23																								
	X6020088	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																								
	X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	448,624	448,624																								

PATRICK ENGINEERING INC.
4970 VARSITY DRIVE
LISLE, IL 60532
patrickengineering.com

USER NAME = Rdwy.Lisle	DESIGNED -	REVISED -
PLOT CONFIG= PDF(Grey_Large).plt	DRAWN -	REVISED -
PLOT SCALE = 1:50	CHECKED -	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/3/2010	REVISED -

Illinois Department of Transportation

ILLINOIS ROUTE 53
SUMMARY OF QUANTITIES

SCALE: NA | SHEET SOQ-16 OF 20 | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DUPAGE	781	19

CONTRACT NO. 60477

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

q:\idot\9356_a0_(i153)\drawings\cadd sheets\D19139797-sht-SOQ_004-023.dgn