


ARMY TRAIL RD EARTHWORK			UNDERCUT FOR PGE REPLACEMENT			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)			
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	
7+00.00	TO	8+00.00	0.00	0.00	0.00	11.56	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+00.00	TO	9+00.00	0.00	0.00	0.00	11.56	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9+00.00	TO	10+00.00	0.00	117.33	0.00	14.22	0.00	0.00	0.00	89.40	0.00	0.00	75.99	0.00	0.00	1.02	0.00	0.00	74.97	0.00	0.00
10+00.00	TO	11+00.00	0.00	359.19	0.00	26.62	0.00	0.00	0.00	236.72	0.00	0.00	201.21	0.00	0.00	5.34	0.00	0.00	195.87	0.00	0.00
11+00.00	TO	12+00.00	0.00	484.34	0.00	52.97	0.00	0.00	0.00	326.94	0.00	0.00	277.89	0.00	0.00	4.55	0.00	0.00	273.35	0.00	0.00
12+00.00	TO	12+58.00	0.00	277.59	0.00	52.77	0.00	0.00	0.00	152.48	0.00	0.00	129.61	0.00	0.00	6.75	0.00	0.00	122.86	0.00	0.00
12+58.00	TO	13+00.00	0.00	196.11	0.00	33.66	0.00	0.00	0.00	74.37	0.00	0.00	63.21	0.00	0.00	13.22	0.00	0.00	49.99	0.00	0.00
13+00.00	TO	13+61.40	0.00	284.17	0.00	39.10	0.00	0.00	0.00	114.32	0.00	0.00	97.17	0.00	0.00	18.56	0.00	0.00	78.62	0.00	0.00
13+61.40	TO	16+54.08	0.00	1318.98	0.00	212.74	0.00	0.00	13.55	354.09	0.00	11.52	300.98	0.00	0.00	167.83	0.00	11.52	133.15	0.00	0.00
16+54.08	TO	17+00.00	0.00	200.73	0.00	29.27	0.00	0.00	7.40	37.06	0.00	6.29	31.50	0.00	0.00	29.72	0.00	6.29	1.78	0.00	0.00
17+00.00	TO	17+19.64	0.00	86.87	0.00	9.17	0.00	0.00	3.38	22.87	0.00	2.88	19.44	0.00	0.00	6.83	0.00	2.88	12.61	0.00	0.00
17+19.64	TO	17+70.08	0.00	224.95	0.00	30.05	0.00	0.00	5.96	51.09	0.00	5.07	43.43	0.00	0.00	12.56	0.00	5.07	30.86	0.00	0.00
17+70.08	TO	18+00.00	0.00	132.73	0.00	17.46	0.00	0.00	5.37	20.48	0.00	4.57	17.41	0.00	0.00	5.52	0.00	4.57	11.89	0.00	0.00
18+00.00	TO	19+00.00	0.00	416.85	0.00	54.01	0.00	0.00	16.84	115.55	0.00	14.32	98.21	0.00	2.88	65.35	0.00	11.44	32.86	0.00	0.00
19+00.00	TO	19+38.21	0.00	143.91	0.00	17.76	0.00	0.00	1.90	68.53	0.00	1.61	58.25	0.00	1.10	33.99	0.00	0.51	24.26	0.00	0.00
19+38.21	TO	19+68.23	0.00	109.96	0.00	18.08	0.00	0.00	1.51	59.56	0.00	1.28	50.63	0.00	1.78	28.42	0.00	-0.50	22.21	0.00	0.00
19+68.23	TO	20+00.00	0.00	113.58	0.00	24.97	0.00	0.00	2.84	66.21	0.00	2.42	56.28	0.00	1.90	35.09	0.00	0.52	21.19	0.00	0.00
20+00.00	TO	21+00.00	0.00	172.48	0.00	66.32	0.00	0.00	3.93	279.93	0.00	3.34	237.94	0.00	0.06	63.29	0.00	3.28	174.65	0.00	0.00
21+00.00	TO	22+00.00	0.00	0.00	0.00	35.03	0.00	0.00	0.00	174.64	0.00	0.00	148.44	0.00	0.00	13.12	0.00	0.00	135.32	0.00	0.00
22+00.00	TO	23+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTALS =			0.00	4639.77	0.00	757.31	0.00	0.00	62.69	2244.23	0.00	53.28	1907.60	0.00	7.71	511.15	0.00	45.57	1396.44	0.00	

PATRICK ENGINEERING INC.
4970 VARSITY DRIVE
LISLE, IL 60532
patrickengineering.com

USER NAME = Rdwj.Lisle
PLOT CONFIG = PDF(Grey_Large).plt
PLOT SCALE = 1:50
PLOT DATE = 12/3/2010

DESIGNED -
DRAWN -
CHECKED -
DATE - 12/3/2010

REVISED -
REVISED -
REVISED -
REVISED -



**ARMY TRAIL
EARTHWORK SCHEDULE**

SCALE: 1"=50' SHEET SCH-10 OF 18 STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B		781	33
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO.				