


LAKE ST EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
12+00.00	TO	13+00.00	14.50	0.00	0.00	0.00	75.10	0.00	0.00	63.84	0.00	0.00	18.47	0.00	0.00	45.36	0.00
13+00.00	TO	14+00.00	20.81	0.00	0.00	0.00	171.58	0.00	0.00	145.85	0.00	0.00	30.36	0.00	0.00	115.48	0.00
14+00.00	TO	15+00.00	12.01	0.00	0.00	0.00	162.71	0.00	0.00	138.31	0.00	0.00	27.28	0.00	0.00	111.03	0.00
15+00.00	TO	15+90.00	5.13	0.00	0.00	0.00	59.61	0.00	0.00	50.67	0.00	0.00	13.85	0.00	0.00	36.82	0.00
15+90.00	TO	17+00.00	20.83	0.00	0.00	0.00	137.28	0.00	0.00	116.68	0.00	0.00	13.08	0.00	0.00	103.61	0.00
17+00.00	TO	18+00.00	54.09	0.00	0.00	1.44	311.20	0.00	1.23	264.52	0.00	0.83	18.54	0.00	0.39	245.99	0.00
18+00.00	TO	18+57.19	47.74	0.00	0.00	4.29	265.74	0.00	3.65	225.88	0.00	0.48	3.80	0.00	3.17	222.08	0.00
18+57.19	TO	19+00.00	38.23	0.00	0.00	4.97	250.64	0.00	4.23	213.04	0.00	0.17	1.06	0.00	4.05	211.98	0.00
19+00.00	TO	23+00.00	313.52	0.00	0.00	22.22	1272.81	0.00	18.89	1081.89	0.00	1.63	398.30	0.00	17.26	683.60	0.00
23+00.00	TO	23+54.01	41.99	0.00	0.00	0.59	7.86	0.00	0.50	6.68	0.00	0.39	111.35	0.00	0.11	-104.67	0.00
23+54.01	TO	23+84.73	18.46	0.00	0.00	0.33	3.42	0.00	0.28	2.90	0.00	0.22	68.55	0.00	0.06	-65.65	0.00
23+84.73	TO	24+00.00	6.78	0.00	0.00	0.55	1.42	0.00	0.47	1.20	0.00	0.00	41.62	0.00	0.47	-40.41	0.00
24+00.00	TO	25+00.00	68.46	0.00	0.00	4.57	8.54	0.00	3.89	7.26	0.00	1.77	371.69	0.00	2.12	-364.43	0.00
25+00.00	TO	26+00.00	93.62	0.00	0.00	17.44	44.35	0.00	14.83	37.70	0.00	1.77	304.70	0.00	13.06	-267.00	0.00
26+00.00	TO	27+00.00	103.62	0.00	0.00	25.60	103.56	0.00	21.76	88.03	0.00	0.00	163.59	0.00	21.76	-75.56	0.00
27+00.00	TO	27+92.56	66.63	0.00	0.00	8.46	117.81	0.00	7.19	100.14	0.00	0.00	104.88	0.00	7.19	-4.75	0.00
TOTALS =			926.42	0.00	0.00	90.47	2993.63	0.00	76.90	2544.59	0.00	7.26	1691.12	0.00	69.64	853.47	0.00

PATRICK ENGINEERING INC.
 4970 VARSITY DRIVE
 LISLE, IL 60532
 patrickengineering.com

USER NAME = Rdwy_Lisle
 PLOT CONFIG = PDF(Greg_Large).plt
 PLOT SCALE = 1:50
 PLOT DATE = 12/3/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE - 12/3/2010

REVISED -
 REVISED -
 REVISED -
 REVISED -



**LAKE STREET
 EARTHWORK SCHEDULE**

SCALE: 1"=50' SHEET SCH-11 OF 18 STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DUPAGE	781	34
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO.				