


NORDIC RD EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
			CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
8+01.44	TO	9+00.00	32.59	0.00	0.00	0.00	0.00	43.81	0.00	0.00	37.24	0.00	0.00	22.12	0.00	0.00	15.12
9+00.00	TO	9+28.88	17.29	0.00	0.00	0.00	0.00	20.37	0.00	0.00	17.32	0.00	0.00	12.24	0.00	0.00	5.08
9+28.88	TO	10+00.00	43.28	0.00	0.00	0.00	0.00	70.05	0.00	0.00	59.54	0.00	0.00	23.81	0.00	0.00	35.73
10+00.00	TO	10+65.27	33.02	0.00	0.00	0.00	0.00	71.05	0.00	0.00	60.40	0.00	0.00	8.89	0.00	0.00	51.51
10+65.27	TO	12+00.00	45.11	0.00	0.00	9.69	0.00	97.23	8.24	0.00	82.65	2.84	0.00	4.19	5.39	0.00	78.45
12+00.00	TO	13+00.00	40.34	0.00	0.00	11.99	0.00	116.13	10.19	0.00	98.71	7.69	0.00	26.99	2.50	0.00	71.72
13+00.00	TO	13+57.97	29.67	0.00	0.00	5.15	0.00	111.50	4.38	0.00	94.77	9.30	0.00	20.20	-4.92	0.00	74.57
13+57.97	TO	14+00.00	25.58	0.00	0.00	2.43	0.00	121.82	2.06	0.00	103.55	23.15	0.00	7.06	-21.08	0.00	96.48
14+00.00	TO	16+00.00	125.61	0.00	0.00	3.37	365.89	355.85	2.86	311.01	302.47	89.22	47.76	11.83	-86.36	263.25	290.64
16+00.00	TO	16+73.12	46.71	0.00	0.00	0.00	177.87	0.00	0.00	151.19	0.00	0.00	31.74	0.00	0.00	119.45	0.00
16+73.12	TO	17+00.00	15.89	0.00	0.00	0.00	34.33	0.00	0.00	29.18	0.00	0.00	13.54	0.00	0.00	15.64	0.00
17+00.00	TO	17+34.39	16.99	0.00	0.00	0.00	39.35	0.00	0.00	33.45	0.00	0.00	21.66	0.00	0.00	11.79	0.00
17+34.39	TO	17+52.19	7.36	0.00	0.00	0.00	17.50	0.00	0.00	14.88	0.00	0.00	8.55	0.00	0.00	6.33	0.00
17+52.19	TO	18+00.00	8.07	0.00	0.00	0.00	24.53	0.00	0.00	20.85	0.00	0.00	7.61	0.00	0.00	13.24	0.00
TOTALS =			487.52	0.00	0.00	32.64	659.48	1007.81	27.74	560.56	856.64	132.21	130.86	137.34	-104.47	429.69	719.30

PATRICK ENGINEERING INC.
 4970 VARSITY DRIVE
 LISLE, IL 60532
 patrickengineering.com

USER NAME = Rdky.Lisle
 PLOT CONFIG = PDF(Grey, Large).plt
 PLOT SCALE = 1:50
 PLOT DATE = 12/3/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE - 12/3/2010

REVISED -
 REVISED -
 REVISED -
 REVISED -



NORDIC ROAD EARTHWORK SCHEDULE
 SCALE: 1"=50' SHEET SCH-12 OF 18 STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DUPAGE	781	35
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		