

STREET	* UNDERCUT FOR PGE REPLACEMENT			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
ARDMORE AVE.	0.00	0.00	0.00	298.33	0.00	0.00	344.98	535.04	352.38	293.23	454.78	299.52	1.07	125.55	141.73	292.16	329.23	157.80
ARMY TRAIL RD.	0.00	4,639.77	0.00	757.31	0.00	0.00	62.69	2,244.23	0.00	53.28	1,907.60	0.00	7.71	511.15	0.00	45.57	1,396.44	0.00
BRYN MAWR AVE.	0.00	0.00	0.00	431.21	0.00	0.00	657.97	1016.35	1067.31	559.27	863.90	907.22	2.20	90.22	63.05	557.07	773.68	844.17
IL 53	0.00	6403.68	4026.02	21985.20	4447.80	3991.16	3315.22	20031.51	17492.79	2817.94	17026.78	14868.87	7161.47	21714.36	9725.67	-4343.53	-4687.57	5143.20
IRVING PARK RD.	0.00	994.55	0.00	1,562.44	0.00	0.00	222.97	5,430.86	0.00	189.52	4,616.23	0.00	22.09	1,086.30	0.00	167.43	3,529.92	0.00
LAKE ST.	0.00	0.00	0.00	926.42	0.00	0.00	90.47	2,993.63	0.00	76.90	2,544.59	0.00	7.26	1,691.12	0.00	69.64	853.47	0.00
NORDIC RD.	0.00	0.00	0.00	487.52	0.00	0.00	32.64	659.48	1007.81	27.74	560.56	856.64	132.21	130.86	137.34	-104.47	429.69	719.30
NORWOOD AVE.	0.00	0.00	0.00	572.23	0.00	0.00	130.86	322.39	1705.50	111.23	274.03	1449.68	200.23	213.00	5.88	-89.00	61.03	1443.80
THORNDALE AVE.	0.00	0.00	0.00	692.98	0.00	0.00	812.98	1798.09	913.54	691.03	1528.37	776.51	13.40	93.06	191.03	677.64	1435.31	585.48
TOTALS=	0.00	12038.01	4026.02	27713.65	4447.80	3991.16	5670.77	35031.57	22539.34	4820.15	29776.84	19158.44	7547.65	25655.62	10264.70	-2727.49	4121.22	8893.74



** REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL= 52,217 CU YD

EARTH EXCAVATION= 63,245 CU YD

FURNISHED EXCAVATION= 2,730 CU YD

* PGE REPLACEMENT SHALL BE PAID FOR AS POROUS GRANULAR EMBANKMENT, SUBGRADE (CU YD).
SEE THE PLAN AND PROFILE SHEETS AND THE SCHEDULE OF QUANTITIES FOR LOCATIONS AND THICKNESSES.

** THIS QUANTITY INCLUDES THE VOLUMES OF UNDERCUT FOR PGE REPLACEMENT AND 6" TOPSOIL REMOVAL.

 PATRICK ENGINEERING INC. 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = Rdw.Lisle	DESIGNED -	REVISED - 10/12/2010	 Illinois Department of Transportation	EARTHWORK SCHEDULE			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT CONFIG= PDF(Greg_Large).plt	DRAWN -	REVISED -					2578	532B	DUPAGE	781	41
PLOT SCALE = 1:50	CHECKED -	REVISED -			SCALE: 1"=50'	SHEET SCH-18 OF 18	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			
PLOT DATE = 12/3/2010	DATE - 12/3/2010	REVISED -							CONTRACT NO.			