



THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACTOR'S BID PRICE.

- 3 EACH SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED
- 5 EACH SIGNAL HEAD, 1-FACE, 3-SECTION, BRACKET MOUNTED
- 1 EACH SIGNAL HEAD, 2-FACE, 3-SECTION, BRACKET MOUNTED
- 3 EACH TRAFFIC SIGNAL BACKPLATE

NOTE 1: THE EXISTING 3C NO. 20 CABLE SHALL BE USED FOR TEMPORARY LIGHT DETECTOR TO BE MOUNTED ON THE TEMPORARY SIGNAL AT THE EAST RAMPS FOR THE TRAFFIC SIGNAL INSTALLATION AT THE WEST RAMP. ADDITIONAL CABLE SHALL BE SPLICED AS NEEDED. AFTER THE PERMANENT TRAFFIC SIGNAL INSTALLATION AT THE EAST RAMPS AND ARMY TRAIL ROAD IS OPERATIONAL, THE EXISTING 3C NO. 20 CABLE USED AS A TEMPORARY CABLE SHALL BE REMOVED (TOTAL 1701 FT.). THE REMOVAL OF THE EXISTING CABLE SHALL BE PAID FOR SEPARATELY AS "REMOVE EXISTING CABLE FROM CONDUIT".

FILE NAME =	USER NAME = #USER#	DESIGNED - PKG	REVISED -
#FILE#		DRAWN - MAA, EA	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - PKG, EA	REVISED -
	PLOT DATE = #DATE#	DATE - 5/10/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC SIGNAL MODIFICATION PLAN  
ARMY TRAIL RD. AT RAMP "A" (WEST RAMP)**

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DuPage	781	512
CONTRACT NO. 60477				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				