

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0003	TRAFFIC SIGNAL 0021 80% FED. 10% STATE 10% VILLAGE OF STEAMWOOD	PRE EMPYORS 0021 100% VILLAGE OF STEAMWOOD				CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0003	TRAFFIC SIGNAL 0021 80% FED. 10% STATE 10% VILLAGE OF STEAMWOOD	PRE EMPYORS 0021 100% VILLAGE OF STEAMWOOD			
20200100	EARTH EXCAVATION	CU YD	378	378					60107600	PIPE UNDERDRAINS 4"	FOOT	75	75						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	226	226					60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3						
20400800	FURNISHED EXCAVATION	CU YD	37	37					60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2						
20800150	TRENCH BACKFILL	CU YD	200	200					60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	380	380					60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7	7					60500050	REMOVING CATCH BASINS	EACH	4	4						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4					60600605	CONCRETE CURB, TYPE B	FOOT	130	130						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3					60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	100	100						
25200110	SODDING, SALT TOLERANT	SQ YD	380	380					60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	500	500						
25200200	SUPPLEMENTAL WATERING	UNIT	4	4					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
28000400	PERIMETER EROSION BARRIER	FOOT	520	520					67100100	MOBILIZATION	L SUM	1	1						
28000510	INLET FILTERS	EACH	9	9					70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1						
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	155	155					70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1						
35501323	HOT-MIX ASPHALT BASE COURSE, 9 3/4"	SQ YD	542	542					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6					70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
40600300	AGGREGATE (PRIME COAT)	TON	28	28					70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11					70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					70300100	SHORT TERM PAVEMENT MARKING	FOOT	300	300						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	110	110					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	217.8	217.8						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	20	20					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1634	1634						
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	830	830					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1500	1500						
42001300	PROTECTIVE COAT	SQ YD	590	590					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	140	140						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	3070	3070					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	400	400						
42400800	DETECTABLE WARNINGS	SO FT	60	60					* 72000200	SIGN PANEL - TYPE 2	SO FT	19.5	19.5						
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	6730	6730					* 72400720	RELOCATE SIGN PANEL - TYPE 2	SO FT	20	20						
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	1825	1825					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	217.8	217.8						
44000300	CURB REMOVAL	FOOT	140	140					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1634	1634						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	530	530					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1500	1500						
44000600	SIDEWALK REMOVAL	SO FT	2255	2255					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140	140						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	585	585															
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	288	288															
55100500	STORM SEWER REMOVAL 12"	FOOT	26	26															
60107600	PIPE UNDERDRAINS 4"	FOOT	75	75															

* SPECIALTY ITEMS

FILE NAME =	USER NAME = gulloumefp	DESIGNED -	REVISED -
c:\pwworkspace\gulloumefp\dms93544\PI\33508-Design.dgn		DRAWN -	REVISED -
PLOT SCALE = 50,0000 1/16 IN.		CHECKED -	REVISED -
PLOT DATE = 12/16/2010		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.P. RTE. 362	SECTION 0105 N-2	COUNTY COOK	TOTAL SHEETS 41	SHEET NO. 3
CONTRACT NO. 60J09				