

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0003	TRAFFIC SIGNAL 0021 80% FED. 10% STATE 10% VILLAGE OF STEAMWOOD	PRE EMPTORS 0021 100% VILLAGE OF STREAMWOOD				CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0003	TRAFFIC SIGNAL 0021 80% FED. 10% STATE 10% VILLAGE OF STEAMWOOD	PRE EMPTORS 0021 100% VILLAGE OF STREAMWOOD			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	60	60					88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10					
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	250		250				88500100	INDUCTIVE LOOP DETECTOR	EACH	10		10					
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	36		36				88600100	DETECTOR LOOP, TYPE I	FOOT	117		117					
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	33		33				88700200	LIGHT DETECTOR	EACH	2				2			
81400100	HANDHOLE	EACH	1		1				88700300	LIGHT DETECTOR AMPLIFIER	EACH	1				1			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	266		266				88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8					
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1				89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1					
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1837		1837					
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1179		1179				89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1					
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1753		1753				89502380	REMOVE EXISTING HANDHOLE	EACH	1		1					
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	908		908				89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	3		3					
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	928		928				X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2						
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1299		1299				X5539700	STORM SEWERS TO BE CLEANED	FOOT	50	50						
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1		1				X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5						
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1				X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1					
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1		1				89301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	476		476					
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4				X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	296		296					
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26		26				X8950200	REBUILD EXISTING HANDHOLE	EACH	1		1					
87900200	DRILL EXISTING HANDHOLE	EACH	4		4				Z0001050	AGGREGATE SUBGRADE 12"	SO YD	542	542						
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6		6				Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	16	16						
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2				Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8						
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2		2				Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1		1					
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1				Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1					
88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2		2														

* SPECIALTY ITEMS
 Δ Non-participating