

SUMMARY OF QUANTITIES

*URBAN
100% STATE*

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	BRIDGE RECONSTRUCTION 0011	LANDSCAPING 0031
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	267			267
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	58			58
20101100	TREE TRUNK PROTECTION	EACH	17	17		
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	7			7
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	10			10
20200100	EARTH EXCAVATION	CU YD	1837	1837		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100		
20300100	CHANNEL EXCAVATION	CU YD	80			80
20400800	FURNISHED EXCAVATION	CU YD	100	100		
20800150	TRENCH BACKFILL	CU YD	467	467		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	144	144		
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3630			3630
* 25000210	SEEDING, CLASS 2A	ACRE	0.50			0.50
* 25000314	SEEDING, CLASS 4B	ACRE	0.25			0.25
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68			68
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68			68
* 25100630	EROSION CONTROL BLANKET	SQ YD	3630	3630		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75	75		
28000305	TEMPORARY DITCH CHECKS	FOOT	42	42		
28000400	PERIMETER EROSION BARRIER	FOOT	852	852		
28000510	INLET FILTERS	EACH	3	3		
* 25100115	MULCH, METHOD 2	ACRE	1			1
28100107	STONE RIPRAP, CLASS A4	SQ YD	110		110	
28200200	FILTER FABRIC	SQ YD	110		110	
31101400	SUB BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1013	1013		

* INDICATES SPECIALTY ITEMS

*URBAN
100% STATE*

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	BRIDGE RECONSTRUCTION 0011	LANDSCAPING 0031
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	541	541		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	90	90		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1931	1931		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	73	73		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	386	386		
44000100	PAVEMENT REMOVAL	SQ YD	3449	3449		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	449	449		
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	651	651		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1013	1013		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	104	104		
50200100	STRUCTURE EXCAVATION	CU YD	560		560	
50300225	CONCRETE STRUCTURES	CU YD	490.9		490.9	
50300300	PROTECTIVE COAT	SQ YD	178		178	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	59,260		59,260	
50800515	BAR SPLICERS	EACH	142		142	
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	1587		1587	
51202305	DRIVING PILES	FOOT	1587		1587	
51203200	TEST PILE METAL SHELLS	EACH	2		2	
51500100	NAME PLATES	EACH	1		1	
54213870	STEEL END SECTIONS 15"	EACH	1	1		
54213873	STEEL END SECTIONS 18"	EACH	1	1		
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	47	47		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	53	53		
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	651	651		

* INDICATES SPECIALTY ITEMS

DATE: _____ BY: _____
 SURVEYED _____ ALIGNED _____ CHECKED _____
 PLAN NOTE BOOK _____
 NO. _____

DATE: _____ BY: _____
 SURVEYED _____ ALIGNED _____ CHECKED _____
 PLAN NOTE BOOK _____
 NO. _____

...@D160J67-shr-S001.dgn
 12/23/2010
 10:03:47 AM



DESIGNED	JRB	REVISED	-
DRAWN	JRB	REVISED	-
CHECKED	RJD	REVISED	-
DATE	JANUARY 3, 2011	REVISED	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 176 OVER EAST SKOKIE DITCH
SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1238	C-B-1	LAKE	61	3
ILLINOIS FED. AID PROJECT				CONTRACT NO. 60J67

Rev.