

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				ACNHE ROADWAY US 45 80% FED 20% STATE 0003	ACCMF ROADWAY PED PATH 80% FED 20% STATE 0028	ACNHE SN 016-6201 80% FED 20% STATE 0010	ACCMF SN 016-7702 80% FED 20% STATE 0008	ACNHE RETAINING WALL 80% FED 20% STATE 0040
20100500	TREE REMOVAL, ACRES	ACRE	0.50	0.50				
20200100	EARTH EXCAVATION	CU YD	598	555	43			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,852	1,313	239			
20400800	FURNISHED EXCAVATION	CU YD	20,069	18,883	1,986			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	625			625		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,087	2,087				
25000210	SEEDING, CLASS 2A	ACRE	0.50	0.50				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	65	65				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	65	65				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	65	65				
25100115	MULCH, METHOD 2	ACRE	3	3				
25100630	EROSION CONTROL BLANKET	SQ YD	1,810	1,810				
25200110	SODDING, SALT TOLERANT	SQ YD	1,455	1,455				
25200200	SUPPLEMENTAL WATERING	UNIT	27	27				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	265	265				
28000305	TEMPORARY DITCH CHECKS	FOOT	155	155				
28000400	PERIMETER EROSION BARRIER	FOOT	930	930				
28000510	INLET FILTERS	EACH	4	4				
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1,454		1,454			
40600300	AGGREGATE (PRIME COAT)	TON	3		3			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	120		120			
42001300	PROTECTIVE COAT	SQ YD	509	509				
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1,285		1,285			
44000100	PAVEMENT REMOVAL	SQ YD	2,048	2,048				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,275	1,275				
50102400	CONCRETE REMOVAL	CU YD	225			114		111
50200100	STRUCTURE EXCAVATION	CU YD	6,200			2,531	493	3,176
50300225	CONCRETE STRUCTURES	CU YD	2,902.9			1,643.3	354.7	904.9
50300254	RUBBED FINISH	SQ FT	337				337	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	7.3				7.3	
50300285	FORM LINER TEXTURED SURFACE	SQ FT	3,200					3,200
50500305	ERECTING STRUCTURAL STEEL	L SUM	1			1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	236,480			115,200	34,500	86,780
50900805	PEDESTRIAN RAILING	FOOT	280					280

\* DENOTES SPECIALTY ITEM

VOP = VILLAGE OF ORLAND PARK

FILE NAME =	USER NAME = TKL,eq
D:\6064-SHT-50001.dgn	
PLOT SCALE = 1/8"	
PLOT DATE = 12/	

DESIGNED - MJT	REVISED -
DRAWN - MJT	REVISED -
CHECKED - TRK	REVISED -
DATE - 12/17/10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	73 R-B	COOK	136	4
SQ-01			CONTRACT NO. 60K64	
ILLINOIS FED. AID PROJECT				

Rev.