

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				URBAN		ACNHE	ACNHE	ACNHE
				ROADWAY US 45	ROADWAY PED PATH	SN 016-6201	SN 016-7702	RETAINING WALL
80% FED	80% FED	80% FED	80% FED	80% FED				
20% STATE	20% STATE	20% STATE	20% STATE	20% STATE				
0003	0028	0010	0008	0040				
50901760	PIPE HANDRAIL	FOOT	505			441		64
51201600	FURNISHING STEEL PILES HP12X53	FOOT	10,708				4343	6,365.0
51202100	FURNISHING STEEL PILES HP14X117	FOOT	17,196.0			17,196.0		
51202305	DRIVING PILES	FOOT	27,904			17,196.0	4343	6,365.0
51203600	TEST PILE STEEL HP12X53	EACH	9				3	6
51204100	TEST PILE STEEL HP14X117	EACH	3			3		
51204650	PILE SHOES	EACH	88				88	
51500100	NAME PLATES	EACH	2			1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	46.5				46.5	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	32			32		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	25	25				
52100540	ANCHOR BOLTS, 1 1/2"	EACH	16			16		
58700300	CONCRETE SEALER	SO FT	10,600			7,266	3,334	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	1,469			474	186	809
60100905	PIPE DRAINS 4"	FOOT	130			30		100
60200905	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	1	1				
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5				
66400105	CHAIN LINK FENCE, 4'	FOOT	137	137				
60602800	CONCRETE GUTTER, TYPE B	FOOT	415	415				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,500	2,500				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,275	1,275				
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
63200310	GUARDRAIL REMOVAL	FOOT	690	690				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1				
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	8	8				
67100100	MOBILIZATION	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2,056	2,056				
70400600	RELOCATE TEMPORARY CONCRETE BARRIER, STATE OWNED	FOOT	2,000.0	2,000.0				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,000.0	1,000.0				
* 72000200	SIGN PANEL - TYPE 2	SO FT	31			31		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,100	4,100				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	70	70				
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	98	98				
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1		
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	31			31		
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	16			16		
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	28			28		
* 81017505	CONDUIT IN TRENCH, 3/4" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	59			59		
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	80	80				
* 81017515	CONDUIT IN TRENCH, 1 1/4" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	524			524		
* 81017535	CONDUIT IN TRENCH, 3" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	314			314		
* 81017525	CONDUIT IN TRENCH, 2" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	122			122		

\* DENOTES SPECIALTY ITEM

VOP = VILLAGE OF ORLAND PARK

FILE NAME = D160K64-SHT-S0002.dgn	USER NAME = TKluegel	DESIGNED - MJT	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 330	SECTION 73 R-B	COUNTY COOK	TOTAL SHEETS 136	SHEET NO. 5
PLOT SCALE = 1:150	DRAWN - MJT	CHECKED - TRK	REVISED -		SCALE: N.T.S.	SHEET NO. 2 OF 4 SHEETS	STA. TO STA.	<b>SQ-02</b>		CONTRACT NO. 60K64		
PLOT DATE = 12/16/10	DATE - 12/17/10	REVISED -			ILLINOIS FED. AID PROJECT							

Rev.