

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				ACNHF ROADWAY US 45	ACCMF ROADWAY PED PATH	ACNHF SN 016-6201	ACCMF SN 016-7702	ACNHF RETAINING WALL
				80% FED 20% STATE 0003	80% FED 20% STATE 0028	80% FED 20% STATE 0010	80% FED 20% STATE 0008	80% FED 20% STATE 0040
81017530	CONDUIT IN TRENCH, 2 1/2" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	28					
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	594	594				
81100510	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	223		223			
81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	118	118				
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	198		198			
81200260	CONDUIT EMBEDDED IN STRUCTURE, 3" DIA., PVC	FOOT	213	213				
81200220	CONDUIT EMBEDDED IN STRUCTURE, 1 1/2" DIA., PVC	FOOT	355		355			
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	8	8				
81300720	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 12" X 8"	EACH	4					
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	8	8				
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	3,408	3,218	195			
81300945	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 8"	EACH	8	8				
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	8,943		8,943			
81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	46		46			
81702170	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2/0	FOOT	184		184			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,459		1,459			
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	48		48			
84200804	REMOVAL OF POLE FOUNDATION	EACH	2		2			
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2			
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1		1			
89502300	REMOVE EXISTING HANDHOLE	EACH	1					
X0322400	PILE EXTRACTION	EACH	27			27		
X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SO FT	2,010				2,010	
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3	3				
X0324397	RELOCATE ELECTRIC SERVICE	EACH	1		1			
X0324431	TEMPORARY SOIL RETENTION SYSTEM (TO REMAIN IN PLACE)	SO FT	1015			272	743	
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SO YD	1,190	1,190				
X0325444	TEMPORARY CONCRETE BARRIER (INSTALL ONLY)	FOOT	1000	1000				
X0326542	METAL GRATING	L SUM	1			1		
X2020502	BRACED EXCAVATION	CU YD	84			84		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,722				273	1,449
X5150110	NAME PLATES (SPECIAL)	EACH	1			1		
A X5539700	STORM SEWERS TO BE CLEANED	FOOT	200	200				
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	6,205	6,205				
X8140230	HANDHOLE, COMPOSITE CONCRETE (SPECIAL)	EACH	1					
X8950090	RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1		1			
X8950215	RELOCATE EXISTING HANDHOLE	EACH	1		1			
XX008438	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1				
XZ127900	RETAINING WALL REMOVAL	FOOT	83		83			
Z0002400	BALLAST	TON	186			186		

* DENOTES SPECIALTY ITEM Δ = Non-participating

VOP = VILLAGE OF ORLAND PARK

FILE NAME D160K64-SHT-S0003.dgn	USER NAME = TKJuser	DESIGNED - MJT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 330	SECTION 73 R-B	TOTAL SHEETS 136	SHEET NO. 6	
PLOT SCALE = 1:50	DRAWN - MJT	CHECKED - TRK	REVISED -					SCALE: N.T.S.	SHEET NO. 3 OF 4 SHEETS	STA. TO STA.	SQ-03	
PLOT DATE = 12/16/10	DATE - 12/17/10	REVISED -	REVISED -		CONTRACT NO. 060K64							
ILLINOIS FED. RD. PROJECT												