

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ACNHE ROADWAY US 45	ACCMF ROADWAY PED PATH	ACNHE SN 016-6201	ACCMF SN 016-7702	ACNHE RETAINING WALL	
				80% FED 20% STATE 0003	80% FED 20% STATE 002B	80% FED 20% STATE 0010	80% FED 20% STATE 0008	80% FED 20% STATE 0040	
Z0007122	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	382						382
<del>Z0013798</del>	<del>CONSTRUCTION LAYOUT</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>					
<del>Z0013796</del>	<del>SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE</del>	<del>SQ YD</del>	<del>595</del>	<del>595</del>					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6		6				
<del>Z0023202</del>	<del>SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING</del>	<del>EACH</del>	<del>17</del>	<del>17</del>					
<del>Z0023206</del>	<del>SEDIMENT CONTROL, SILT FENCE MAINTENANCE</del>	<del>FOOT</del>	<del>175</del>	<del>175</del>					
Z0026407	TEMPORARY SHEET PILING	SO FT	3,212						3,212
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		2				
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		2				
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2		2				
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	772			187	99		486
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Z0061100	SANITARY SEWER, TYPE 3 12"	FOOT	42	42					
Z0062456	TEMPORARY PAVEMENT	SO YD	711	711					
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	3,058			2,822	236		
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOUR</del>							
X6026058	MANHOLES [SANITARY] WITH SPECIAL FRAME AND CLOSED LID	EACH	2	2					
X0327136	ERECTING HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED, 1500K	EACH	4			4			
X0327134	ERECTING HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 1500K	EACH	4			4			
X0327135	ERECTING HIGH LOAD MULTI-ROTATIONAL BEARINGS, NON-GUIDED EXPANSION, 500K	EACH	8			8			
X0327137	DECK WATERPROOFING	SO FT	6,994			6,994			
X0327138	PRECAST ORNAMENTAL FIXTURES	EACH	6				6		
<del>Z0046304</del>	<del>PIPE UNDERDRAINS FOR STRUCTURES 4"</del>	<del>FOOT</del>	<del>486</del>						<del>486</del>
Z0064560	SEGMENTAL BLOCK RETAINING WALL	SO FT	2,850						2,850
X0327139	AGGREGATE COLUMN GROUND IMPROVEMENT	L SUM	1						1
X0327140	REMOVE AND RE-ERECT WATER FEATURE	L SUM	1						1
X0327141	LIGHTING STANDARD, TYPE 4A	EACH	6			6			
X0327142	LIGHTING STANDARD, TYPE 4B	EACH	5			5			
X0327143	RELOCATE EXISTING FOUNTAIN CONTROLLER	L SUM	1			1			
52100580	ANCHOR BOLTS, 2.1/2"	EACH	16			16			
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8	8					

• DENOTES SPECIALTY ITEM     $\Delta$  = Non-participating  
VOP = VILLAGE OF ORLAND PARK

FILE NAME = D160K64-SHT-S0004.dgn	USER NAME = TKIuegei	DESIGNED - MJT	REVISED -
		DRAWN - MJT	REVISED -
		CHECKED - TRK	REVISED -
		DATE - 12/17/10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCALE: N.T.S.		SHEET NO. 4 OF 4 SHEETS		STA. TO STA.
<b>SUMMARY OF QUANTITIES</b>				

F.A.P. RTE. 330	SECTION 73 R-B	NO. 7
SO-04		7
ILLINOIS FED. AID PROJECT		

Rev.