

EARTHWORK SCHEDULE WESTBOUND TRACK

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
EAST OF BRIDGE 4192+00.00	4196+00.00	0	78	0	156	-156
WEST OF BRIDGE 4197+00.00	4205+00.00	50	949	43	15,015	-14,972
SUB TOTAL		50	1,027	43	15,171	-15,128

EARTHWORK SCHEDULE PED PATH

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
PAID FOR UNDER CONSTRUCTION CODE 0003 158+00.00	168+00.00	0	249	0	4,016	-4,016
PAID FOR UNDER CONSTRUCTION CODE 0021 168+00.00	171+00.00	43	239	37	2,023	-1,986
SUB TOTAL		43	488	37	6,039	-6,002

EARTHWORK SCHEDULE - TEMPORARY PAVEMENT EXTRACTION

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
290+00.00	295+00.00	242	0	206	0	206
295+00.00	298+50.00	251	0	213	0	213
SUB TOTAL		493	0	419	0	419

EARTHWORK SUMMARY BY LOCATION

LOCATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
WB TRACK	50	1,027	43	15,171	-15,128
PED PATH	43	488	37	6,039	-6,002
APPROACH TO PED PATH (SEE XS-POB)	12	37	10	168	-158
MAINTENANCE OF TRAFFIC	493	0	419	0	419
TOTAL	598	1,552	509	21,378	-20,869

EARTHWORK SUMMARY

DESCRIPTION	QUANTITY	UNIT
EARTH EXCAVATION	598	CU YD
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	1,552	CU YD
FURNISHED EXCAVATION	20,869	CU YD

EROSION CONTROL SCHEDULE

	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET FILTERS
	POUND	FOOT	FOOT	EACH
SHEET				
EC-01 (Top)	-	-	-	-
EC-01 (Bottom)	155	80	185	2
EC-02 (Top)	85	60	660	1
EC-02 (Bottom)	-	-	-	-
SUB-TOTAL	240	140	845	3
AT THE ENGINEER'S DISCRETION	25	15	85	1
GRAND TOTAL	265	155	930	4

* ASSUME 15% FOR SHRINKAGE