SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	80% FED./20% STATE URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005 QUANTITY	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	117	117	
40600300	AGGREGATE (PRIME COAT)	TON	922	922	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	500	500	
40601005	HOT-MIX APSHALT REPLACEMENT OVER PATCHES	TON	1,150	1,150	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	13,237	13,237	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	153,460	153,460	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	6,659	6,659	
44201761	CLASS D PATCHES, TYPE I,10 INCH	SQ YD	164	164	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3,718	3,718	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	323	323	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,112	1,112	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3,202	3,202	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7	
67100100	MOBILIZATION	LSUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION,STANDARD 701421	LSUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION,STANDARD 701306	LSUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION,STANDARD 701336	LSUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION,STANDARD 701701	LSUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	34,086	34,086	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1,554	1,554	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	253,860	253,860	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,406	5,406	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	5,128	5,128	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,792	2,792	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,132	1,132	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,788	3,788	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	777	777	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	126,930	126,930	

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	80% FED./20% STATE URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005 QUANTITY	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,703	2,703	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2,564	2,564	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,396	1,396	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	566	566	
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	219	219	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	6,670	6,670	
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	2,200	2,200	
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	535	535	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,150	1,150	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,150	1,150	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,041	2,041	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	104	104	
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~			
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	545	545	
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6,504	6,504	

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2020, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO.: 184-001005 EXPIRES 4/30/2011
SIGNATURE: 5/28/2020 9:05:23 AM
...\pltcfg\ver\PSF22x34.cfg
...\PLOTS\100153_W02.pltcfg
W:\Construction\W02\100153-\40-Design\W0-02\CADD-SURVEY\DRAWINGS\DGNS\100153-W02-SQQ.sht

BAXTER & WOODMAN Consulting Engineers

DESIGNED - DSH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US ROUTE 14 PARK LANE DRIVE TO IL ROUTE 47 SUMMARY OF QUANTITIES
DRAWN - RKM / CJC	REVISED -		
CHECKED - RWL	REVISED -		
DATE - 11-01-10	FILE - 100153-W02-SQQ.sht		SCALE: NONE STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	28 R-2 RS-3	McHENRY	32	3
C-91-609-10		CONTRACT NO. 60K84		
FED. ROAD DIST. NO. 1	ILLINOIS	FED AID PROJECT		