

INDEX OF SHEETS

LIST OF STATE STANDARDS:

GENERAL NOTES:

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-7	EXISTING AND PROPOSED TYPICAL SECTIONS
8-29	INSIDE SHOULDER AND PAVEMENT MARKING PLANS
30	SUGGESTED TRAFFIC CONTROL AND PROTECTION PLAN
31-64	TRAFFIC SYSTEM CENTER PLANS
65-90	PROPOSED SIGNING PLANS
90A-90C	SINKHOLE REPAIR DETAILS
90D	BARRIER WALL REPAIR DETAIL
91	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT (BD-22)
92	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING (BD-8)
93-94	MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS (TC-12)
95	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES. (TC-17)
96	SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS (TC-18)

STANDARD NO.	DESCRIPTION
000001-00	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
442201-03	CLASS C AND D PATCHES
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
637001-04	CONCRETE BARRIER, DOUBLE FACE, 815 mm (32 in.) HEIGHT
642001-01	SHOULDER RUMBLE STRIPS
701400-05	APPROACH TO LANE CLOSURE, FREEWAY / EXPRESSWAY
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEED > 45 MPH
701901-01	TRAFFIC CONTROL DEVICES
704001-00	TEMPORARY CONCRETE BARRIER

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE AT 800-892-0123 (OR 811) FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF DARIEN, AND THE VILLAGES OF WOODRIDGE, AND BURR RIDGE

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

ANY DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

DRAINAGE ADJUSTMENT OR RECONSTRUCTION LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE EXPRESSWAY TRAFFIC CONTROL SUPERVISOR, STEVE BRINK, AT (847) 705-4155 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT REGINA COOPER EXPRESSWAY FIELD ENGINEER, AT (847) 705-4153, A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTION IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

1.13.11

FILE NAME =	USER NAME = galbanjr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-55 (FROM I-355 TO COUNTY LINE RD.) INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
at:\pwork\pworkdot\galbanjr\0212968\0177410-shit-plan.dgn	PLOT SCALE = 50.7684 / IN.	DRAWN -	REVISED -			55	2010-079-RS	COOK/DUPAGE	90	2	
PLOT DATE = 1/13/2011	DATE -	CHECKED -	REVISED -			CONTRACT NO. 60L67					
						SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		