

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN			
			TOTAL QUANTITY	0005 RESURFACING	0021 SAFETY	0031 LANDSCAPING
<del>20200600</del>	<del>EXCAVATING AND GRADING EXISTING SHOULDER</del>	<del>UNIT</del>	<del>2</del>			<del>2</del>
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	99			99
25000210	SEEDING, CLASS 2A	ACRE	0.02			0.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2			2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2			2
25100630	EROSION CONTROL BLANKET	SQ YD	99			99
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	38	38		
40600300	AGGREGATE (PRIME COAT)	TON	190	190		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	71	71		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	133	133		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,987	3,987		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	47,461	47,461		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	652	652		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	20	20		
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	120	120		
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	164		164	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	738	738		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250		250	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2		2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	112		112	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	104		104	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	24		24	
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	399		399	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11,691	11,691		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	946.4	946.4		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	110,907	110,907		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,655	3,655		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,308	1,308		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	414	414		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,897	3,897		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	473	473		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50,454	50,454		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,028	1,028		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	654	654		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	207	207		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4		4	
* 78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	2		2	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	619	619		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5,031	5,031		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	619	619		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	794	794		
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	198	198		
△ X2503100	MOWING	UNIT	9	9		
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,993	1,993		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	308	308		
Z0055400	RUMBLE STRIP	FOOT	16,512	16,512		
21400100	GRADING AND SHAPING DITCHES	FEET	4300			4300
70100600	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM	1	1		
X4025600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	1	1		

\*Specialty Items  
△Non-participating

FILE NAME =	USER NAME = .USER.	DESIGNED - EF	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 173 - DEEP LAKE ROAD TO W. OF HUNT CLUB ROAD SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 303	SECTION 2010-116-1	COUNTY LAKE	TOTAL SHEETS 23	SHEET NO. 3	Rev.	
*FILEL*	PLOT SCALE = 50' / IN.	DRAWN - EF	REVISED -			SCALE: 50	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 60M50		ILLINOIS FED. AID PROJECT
	PLOT DATE = 1/3/2011	CHECKED - RS	REVISED -									
		DATE - 01-03-2011	REVISED -									