


CONTRACT 60M63
TEMPORARY PAVEMENT MARKING AND TEMPORARY ATTENUATOR SCHEDULE

	PAVEMENT MARKING REMOVAL	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
STAGE	(SQFT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQFT)	(EACH)	(EACH)	(EACH)
1	24,358	9,824	1404	2,528	565	0	3	0	1
2	0	25,060	0	3,063	414	0	0	1	0
3	0	14,029	1517	2,108	414	0	0	0	3
RESURFACING	14,167	186,340	0	6,362	1,142	0	0	0	0
TOTAL	38,525	235,253	2,921	14,081	2,535	0	3	1	4

CONTRACT 60M63
EASTBOUND PAVEMENT MARKING SCHEDULE

LOCATION					THERMOPLASTIC PAVEMENT MARKINGS - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 5"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
ALIGNMENT	DIRECTION	DESCRIPTION	STATION	STATION	(SQFT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)
180	EB	MAINLINE	88+59.21	95+00.00	0	640.8	645	144	0	118	179	0	0	0	0	0	20	0
180	EB	MAINLINE	95+00.00	125+00.00	0	5832	178	227	0	42	757	0	0	0	0	0	76	0
180	EB	MAINLINE	125+00.00	155+00.00	0	6000	0	67	0	0	751	0	0	0	0	0	74	0
180	EB	MAINLINE	155+00.00	185+00.00	0	6000	0	92	0	0	750	0	0	0	0	0	76	0
180	EB	MAINLINE	185+00.00	215+00.00	0	6000	0	99	0	0	743	0	0	0	0	0	76	0
180	EB	MAINLINE	215+00.00	245+00.00	0	6000	0	92	0	0	743	0	0	0	0	0	74	0
180	EB	MAINLINE	245+00.00	275+00.00	0	4372	1884	242	0	63	678	0	645	81	0	161	70	8
180	EB	MAINLINE	275+00.00	305+00.00	0	4578	1914	300	0	0	671	151	297	60	296.25	100	74	6
180	EB	MAINLINE	305+00.00	335+00.00	0	4829	1756	84	0	0	723	0	338	28	0	51	73	4
180	EB	MAINLINE	335+00.00	361+00.00	0	4,447	0	79	0	0	556	0	466	94	413	0	56	0
180	EB	MAINLINE	361+00.00	375+00.00	0	0	0	0	0	0	0	0	2,428	350	1,116	278	0	3
180	EB	MAINLINE	375+00.00	389+00.00	0	0	0	0	0	0	0	0	2,365	350	1,305	208	0	0
180	EB	MAINLINE	389+00.00	419+00.00	0	4,311	0	66	0	0	539	0	844	211	1,071	10	54	0
180	EB	MAINLINE	419+00.00	449+00.00	0	6,000	0	90	0	0	750	0	0	0	0	0	75	0
180	EB	MAINLINE	449+00.00	479+00.00	0	5,664	0	64	0	0	708	0	336	42	0	0	71	3
180	EB	MAINLINE	479+00.00	505+00.00	0	4,768	694	98	0	0	650	0	0	0	36	0	73	0
180	EB	MAINLINE	505+00.00	533+00.00	0	4,225	1,984	551	0	0	700	88	0	0	1,442	0	87	0
180	EB	MAINLINE	533+00.00	544+48.00	0	1,443	959	13	0	0	287	0	0	0	0	0	29	0
TOTAL					0	75,110	10,014	2,308	0	223	10,185	239	7,719	1,216	5,679	808	1,058	24

DESIGNED - LLS/JG	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
USER NAME = pskopek	DRAWN - PMS/DC										REVISED -	80	99-1-RS-4	WILL	116	10
PLOT SCALE = 1/8"=1'	CHECKED - JAL										REVISED -	CONTRACT NO. 60M63				
PLOT DATE = 20-JAN-2011	DATE - 01/21/2011										REVISED -	FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				
FILE NAME = IP_PWP:dms34568\0160M63-shr-schedule.02.dgn		SCALE: N.T.S.		SHEET NO. 2 OF 2 SHEETS		STA. N/A TO STA. N/A										