



**LEGEND:**

- Structural Repair of Concrete (Depth < 5")
- Structural Repair of Concrete (Depth > 5")
- Deck Slab Repair (Partial)
- Approach Slab Repair (Partial Depth)
- Plug Existing Deck Drains

**BILL OF MATERIAL**

ITEM	UNIT	TOTAL
** Deck Slab Repair (Partial)	Sq.Yd.	175
Structural Repair Of Concrete (Depth Equal To Or Less Than 5 inches)	Sq.Ft.	78
Structural Repair Of Concrete (Depth Greater Than 5 inches)	Sq.Ft.	27
Approach Slab Repair (Partial Depth)	Sq.Yd.	5.3
Plug Existing Deck Drains	Each	12
Silicone Joint Sealer, 1.75"	Foot	88

\*\* Work shall be performed in accordance with Special Provision Deck Slab Repair (Special)

**NOTES:**

1. Remove the existing preformed joint seals and replace with silicone joint sealer as detailed in Section A-A.
2. Areas of proposed deck repairs are estimated. Actual type, location and dimensions of deck repairs are to be determined by the Engineer during construction.
3. Removal of Silicone and Neoprene joint shall be included in the cost of Silicone Joint Sealer, 1.75".
4. Contractor may remove and replace guardrail components to facilitate joint replacement work. Cost included with Silicone Joint Sealer, 1.75".

