


CONTRACT 60M65  
WESTBOUND RESURFACING SCHEDULE

LOCATION					POLYMERIZED HMA SURFACE COURSE, SMA, N80	POLYMERIZED HMA BINDER COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL-19.0, N70	HMA SURFACE REMOVAL 2" (SEE NOTE 1)	HMA SURFACE REMOVAL 4"	SHOULDER RUMBLE STRIP
ALIGNMENT	DIRECTION	DESCRIPTION	STATION	STATION	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(FOOT)
I-E0	WB	MAINLINE	88+59.21	95+00.00	199.45	199.45	80.72	134.53	0.00	2741.78	641.1
I-E0	WB	MAINLINE	95+00.00	110+00.00	549.99	549.99	134.74	224.57	0.00	6514.66	2517.6
I-E0	WB	MAINLINE	110+00.00	125+00.00	587.51	587.51	130.85	218.08	0.00	6803.32	3000.0
I-E0	WB	MAINLINE	125+00.00	140+00.00	597.40	597.40	127.03	211.71	0.00	6846.21	3000.0
I-E0	WB	MAINLINE	140+00.00	155+00.00	594.79	594.79	115.06	191.77	0.00	6680.41	3000.0
I-E0	WB	MAINLINE	155+00.00	170+00.00	595.88	595.88	125.56	209.27	0.00	6815.13	3000.0
I-E0	WB	MAINLINE	170+00.00	185+00.00	592.37	592.37	130.90	218.17	0.00	6847.35	3000.0
I-E0	WB	MAINLINE	185+00.00	200+00.00	598.83	598.83	132.18	220.31	0.00	6920.27	3000.0
I-E0	WB	MAINLINE	200+00.00	215+00.00	598.04	598.04	133.21	222.01	0.00	6925.48	3000.0
I-E0	WB	MAINLINE	215+00.00	230+00.00	598.01	598.01	130.85	218.08	0.00	6897.07	3000.0
I-E0	WB	MAINLINE	230+00.00	245+00.00	597.64	597.64	125.74	209.57	0.00	6833.06	3000.0
I-E0	WB	MAINLINE	245+00.00	246+91.80	76.45	76.45	17.59	29.32	0.00	891.98	383.6
I-E0	WB	MAINLINE	250+28.30	260+00.00	422.31	422.31	82.98	104.96	0.00	4520.36	1443.4
I-E0	WB	MAINLINE	260+00.00	269+38.48	464.70	464.70	126.33	93.66	626.18	4818.13	1027.4
I-E0	WB	MAINLINE	269+65.64	275+00.00	206.65	206.65	84.10	74.81	350.14	2379.43	1066.7
I-E0	WB	MAINLINE	275+00.00	285+04.56	464.40	464.40	144.22	115.16	670.75	4968.93	1432.0
I-E0	WB	MAINLINE	288+26.23	290+00.00	93.89	93.89	21.66	17.14	101.54	960.69	173.8
I-E0	WB	MAINLINE	290+00.00	305+00.00	576.16	576.16	224.36	209.19	882.60	6638.45	3000.0
I-E0	WB	MAINLINE	305+00.00	316+63.48	517.05	517.05	172.48	153.68	716.70	5714.23	2830.6
I-E0	WB	MAINLINE	317+66.53	320+00.00	88.59	88.59	30.40	29.31	114.42	1000.30	466.9
I-E0	WB	MAINLINE	320+00.00	335+00.00	581.73	581.73	217.75	211.64	810.44	6705.68	3000.0
I-E0	WB	MAINLINE	335+00.00	348+33.00	481.3	481.3	112.0	186.6	0.0	5,628.2	2666.0
I-E0	WB	MAINLINE	348+33.00	349+65.00	49.3	49.3	11.1	18.5	0.0	572.0	264.0
I-E0	WB	MAINLINE	392+97.80	419+00.00	940.6	940.6	218.6	364.3	0.0	10,987.1	5204.4
I-E0	WB	MAINLINE	419+00.00	449+00.00	1,082.7	1,082.7	252.0	420.0	0.0	12,666.7	6000.0
I-E0	WB	MAINLINE	449+00.00	479+00.00	1,024.1	1,024.1	238.4	397.3	0.0	11,980.9	5675.2
I-E0	WB	MAINLINE	479+00.00	494+94.60	575.5	575.5	133.9	223.2	0.0	6,732.8	3189.2
I-E0	WB	MAINLINE	494+94.60	496+99.80	81.7	81.7	15.3	25.5	0.0	912.0	205.2
I-E0	WB	MAINLINE	496+99.80	503+91.56	335.7	335.7	45.2	75.3	0.0	3,535.7	691.8
LARKIN-D	WB	RAMP	22+86.16	23+42.73	12.0	12.0	3.7	6.2	0.0	150.9	0.0
I-E0	WB	MAINLINE	503+91.56	505+00.00	39.4	39.4	4.3	7.1	0.0	400.0	108.4
I-E0	WB	MAINLINE	505+00.00	515+50.30	379.0	379.0	113.8	189.6	0.0	4,738.8	1653.6
I-E0	WB	MAINLINE	515+50.30	516+23.50	44.9	44.9	5.5	9.1	0.0	465.6	146.4
I-E0	WB	MAINLINE	516+23.50	518+38.80	120.6	120.6	12.1	20.1	0.0	1,220.0	430.6
I-E0	WB	MAINLINE	518+38.80	520+69.80	133.7	133.7	12.9	21.6	0.0	1,347.5	462.0
I-E0	WB	MAINLINE	520+69.80	533+00.00	444.0	444.0	114.1	190.1	0.0	5,322.0	2063.3
I-E0	WB	MAINLINE	533+00.00	533+15.30	5.5	5.5	0.6	0.9	0.0	56.0	15.3
I-E0	WB	MAINLINE	533+15.30	537+85.30	229.6	229.6	31.6	52.7	0.0	2,328.1	470.0
I-E0	WB	MAINLINE	537+85.30	544+48.53	239.4	239.4	55.7	92.9	0.0	2,800.3	1326.5
TOTAL					15,821	15,821	3,850	5,618	4,273	181,268	75,558

NOTES

1. FOR MAINTENANCE OF TRAFFIC (SEE MOT PLANS)

USER NAME = lsupan@hcb	DESIGNED - LLS/JG	REVISED - 02/15/11		<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 10:1	DRAWN - PMS/DC	REVISED -							80	99 (3&4) RS-4	WILL	117	9
PLOT DATE = 15-FEB-2011	CHECKED - JAL	REVISED -			SCALE: N.T.S. SHEET NO. 1 OF 2 SHEETS STA. N/A TO STA. N/A					CONTRACT NO. 60M65			
FILE NAME = IP_PWF\dms34560\0162M65-sht-schedule.01.dgn	DATE - 01/19/2011	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								