



- NOTES**
- ALL EASTBOUND WORK IS IN CONTRACT 60M63 AND ALL WESTBOUND WORK IS IN CONTRACT 60M65.

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, (IL 9.5mm), 1 1/2"
 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 2 1/2"
 HOT-MIX ASPHALT REMOVAL, 4"
 SHOULDER RUMBLE STRIP

POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE STONE MATRIX ASPHALT, N80, 2"
 POLYMERIZED HOT-MIX ASPHALT BINDER COURSE STONE MATRIX ASPHALT, N80, 2"
 HOT-MIX ASPHALT SURFACE REMOVAL, 4"

USER NAME = dcrnkovich	DESIGNED - LLS/JG	REVISED -
PLOT SCALE = 5/8"=1'	DRAWN - PMS/DC	REVISED -
PLOT DATE = 18-JAN-2011	CHECKED - JAL	REVISED -
DATE = 01/19/2011	DATE = 01/19/2011	REVISED -



**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**PROPOSED ROADWAY PLANS
 I-80 MAINLINE**

SCALE: 1"=50' SHEET NO. 5 OF 18 SHEETS STA. 185+00 TO STA. 215+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99 (3&4) RS-4	WILL	117	16
CONTRACT NO. 60M65				
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				