

WESTBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND / DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL - TYPE 3	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE GROUND MOUNTED SIGN SUPPORT	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	SIGN PANEL TYPE 3	MILE POST MARKER ASSEMBLY	METAL POST TYPE B	WOOD SIGN SUPPORT		
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(SQ FT)	(SQ FT)	(SQ FT)	(EACH)	(EACH)	(FOOT)	(SQ FT)	(SQ FT)	(SQ FT)	(EACH)	(FOOT)	(FOOT)		
WB-MP-71	459+57	D10-3a			1.00	5.00										1.00				
WB-WP-72	466+20 LT	OM3-L	1.00	3.00	1.00	3.00				1.00		1.00	3.00					15.2		
WB-WP-73	466+20 RT	OM3-R	1.00	3.00	1.00	3.00				1.00		1.00	3.00					15.2		
WB-WP-74	484+06	R2-1109			4.00	3.00								12.00						
WB-WP-75	484+06	R2-1			4.00	5.00								20.00				20.8		
WB-WP-76	484+06	RED METAL FLAG			1.50	1.50						2.25								
WB-WP-77	484+06	RED METAL FLAG			1.50	1.50						2.25								
WB-MP-78	485+97	D10-3a			1.00	5.00										1.00				
WB-MP-79	486+03	D10-3	1.00	4.00						1.00		1.00								
WB-MP-80	486+47	M3-4	3.00	1.50	3.00	1.50					1.00	1.00	4.50					17.6		
WB-MP-81	486+47	M1-1	3.00	3.00	3.00	3.00							9.00							
WB-WP-82	489+72	R2-4A	4.00	8.00	4.00	8.00			32.00			1.00			32.00			21.3		
WB-WP-83	492+59	R3-4	3.00	3.00	3.00	3.00				1.00		1.00		9.00						
WB-LP-84	497+00	Alcohol Limit	4.00	5.00	4.00	5.00		20.00					20.00							
WB-WP-85	509+77	W4-1	4.00	4.00	4.00	4.00				1.00		1.00		16.00				16.9		
WB-MP-86	512+37	D10-3a			1.00	5.00										1.00				
WB-WP-87	LARKN-DD 5+34	W1-8			2.00	2.50							5.00				9.0	16.0		
WB-WP-88	LARKN-DD 4+71	W1-8			2.00	2.50							5.00				9.0	16.0		
WB-WP-89	LARKN-DD 4+20	W1-8			2.00	2.50							5.00				9.0	16.0		
		ADDITIONAL LOOP CHEVRONS (9)			2.00	2.50							50.00				90.0	144.0		
WB-WP-90	514+42	E5-1a	10.50	5.00	10.50	5.00			52.50			2.00			52.50			41.4		
WB-LP-91	515+85	W13-6	4.00	4.00	4.00	7.00		16.00							28.00					
WB-BM-92	519+43	EXIT 130 A IL-7 SOUTH	15.75	9.84	19.00	13.00			154.98						247.00					
WB-LP-93	522+46	W4-1	4.00	4.00	4.00	4.00		16.00						16.00						
WB-WP-94	LARKN-CC 9+83	W1-8			2.00	2.50							5.00				9.0	16.0		
WB-WP-95	LARKN-CC 9+28	W1-8			2.00	2.50							5.00				9.0	16.0		
WB-WP-96	LARKN-CC 8+71	W1-8			2.00	2.50							5.00				9.0	16.0		
		ADDITIONAL LOOP CHEVRONS (8)			2.00	2.50							40.00				72.0	128.0		
WB-WP-97	528+68	E5-1a	10.50	5.00	10.50	5.00			52.50			2.00			52.50			34.4		
WB-TR-98	534+07	EXIT 127 3 MILES	15.50	12.00	16.00	11.50			186.00						184.00					
WB-TR-99	534+07	EXIT 130 A 1/4 MILE	12.80	11.81	15.00	12.50			151.17						180.00					
WB-TR-100	534+07	EXIT 130 B IL-7 NORTH	15.75	9.84	18.00	11.00			154.98						199.50					
WB-LP-101	534+12	W13-2	5.00	4.00	5.00	4.00		20.00						20.00						
WB-LP-102	536+18	UNIVERSITY OF ST. FRANCIS	5.00	5.00	5.00	5.00			25.00						25.00					
WB-MP-103	538+21	D10-3	1.00	4.00						1.00		1.00								
WB-MP-104	538+77	D10-3a			1.00	5.00										1.00				
WB-WP-105	539+90	ROCKDALE EXIT	10.00	5.00					50.00			2.00								
WB-WP-106	543+83	D9-2	2.50	2.50	2.50	2.50					1.00	1.00	6.25					22.4		
WB-WP-106A	543+83		2.50	2.00	2.50	2.00							5.00							
<b>TOTAL</b>							<b>0.00</b>	<b>158.00</b>	<b>3043.38</b>	<b>11.00</b>	<b>20.00</b>	<b>50.00</b>	<b>364.25</b>	<b>421.50</b>	<b>3196.75</b>	<b>17.00</b>	<b>104</b>	<b>1496</b>		

9.0 0 16.0  
9.0 0 16.0  
9.0 0 16.0  
90.0 0 144.0

9.0 0 16.0  
9.0 0 16.0  
9.0 0 16.0  
72.0 0 128.0

USER NAME = lsupencheck	DESIGNED - LLS/JG	REVISED - 02/15/11
PLOT SCALE = 10:1	DRAWN - PMS/DC	REVISED -
PLOT DATE = 15-FEB-2011	CHECKED - JAL	REVISED -
	DATE - 01/19/2011	REVISED -



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

**SIGNING SCHEDULE OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 2 OF 2 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99 (3&4) RS-4	WILL	117	53
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60M65	