



UNDERSIDE DECK SURVEY

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Cleaning and Painting Exposed Rebar	Sq.Ft.	1044

LEGEND:

Remove all loose concrete, blast clean rebars and re-epoxy coat rebars

NOTES:

1. Areas of proposed deck repairs are estimated. Actual type, location and dimensions of deck repairs are to be determined by the Engineer during construction.

USER NAME =	DESIGNED - GMK	REVISED -
PLOT SCALE =	DRAWN - GFP	REVISED -
PLOT DATE =	CHECKED - WPK/GMK	REVISED -
FILE NAME =	DATE - 01/18/2011	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**UNDERDECK REPAIR PLAN
WESTBOUND I-80 OVER ROCK RUN CREEK
SN-099-0047**

SHEET NO. S-3 OF S-6 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99 (3&4) RS-4	WILL.	117	91
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60M65	