

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					80% FEDERAL 20% STATE		100% LOCAL
					ROADWAY 0004 RURAL	BRIDGE 0011 RURAL	ROADWAY 0004 RURAL
	50105220	PIPE CULVERT REMOVAL	FOOT	33			33
	50200100	STRUCTURE EXCAVATION	CU YD	186		186	
	50200300	COFFERDAM EXCAVATION	CU YD	58		58	
	50202901	COFFERDAM (LOCATION - 1)	EACH	1		1	
	50300225	CONCRETE STRUCTURES	CU YD	85.7		85.7	
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	237.5		237.5	
	50300260	BRIDGE DECK GROOVING	SQ YD	553		553	
	50300265	SEAL COAT CONCRETE	CU YD	24.8		24.8	
	50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2	
	50300300	PROTECTIVE COAT	SQ YD	671		671	
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
	50500505	STUD SHEAR CONNECTORS	EACH	1,920		1,920	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	64,540		64,540	
	50800515	BAR SPLICERS	EACH	72		72	
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	300		300	
	51201800	FURNISHING STEEL PILES HP14X73	FOOT	192		192	
	51202305	DRIVING PILES	FOOT	300		300	
	51203600	TEST PILE STEEL HP12X53	EACH	2		2	
	51204650	PILE SHOES	EACH	12		12	
	51500100	NAME PLATES	EACH	1		1	
	52100520	ANCHOR BOLTS, 1"	EACH	30		30	
	54215547	METAL END SECTIONS 12"	EACH	2			2
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	54		54	
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	6	6		
	60100945	PIPE DRAINS 12"	FOOT	100	100		
	60103500	PIPE DRAINS, CORRUGATED STEEL 12"	FOOT	29	29		
	60107600	PIPE UNDERDRAINS 4"	FOOT	439	439		
	60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
S	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	437.5	437.5		
S	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
S	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
S	63200310	GUARDRAIL REMOVAL	FOOT	1,028	1,028		
S	X665020Z	WOVEN WIRE FENCE REMOVAL	FOOT	320	320		
S	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6	6		

FILE NAME = P:\CBEL\WEST\Projects\2009\09-0082\_Bolton\PH11\CV11\09\B14\S00\_02.dgn



USER NAME = *USER*	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE = 11/9/2010	CHECKED -	REVISED -
	DATE - 10/22/10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 4 OF 73 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2332	03-14185-02-BR	KANE	73	4
CONTRACT NO. 63521				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				