

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					80% FEDERAL 20% STATE		100% LOCAL
					ROADWAY 0004 RURAL	BRIDGE 0011 RURAL	ROADWAY 0004 RURAL
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
	67100100	MOBILIZATION	L SUM	1	1		
	XX008438	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1		
	X7010238	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL MO	5	5		
S	72000100	SIGN PANEL - TYPE 1	SQ FT	35	35		
S	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	7	7		
S	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2		
S	73000100	WOOD SIGN SUPPORT	FOOT	126	126		
S	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6,080	3,160		2,920
S	78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10		
S	78200420	GUARDRAIL MARKERS, TYPE B	EACH	4	4		
S	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
S	A2002716	TREE, CARYA OVATA (SHAGBARK HICKORY), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
S	A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
S	A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
S	A2005670	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	5	5		
S	K1005420	SEEDING (SPECIAL)	SQ YD	150	150		
	X0323017	TEMPORARY INFORMATIONAL SIGNS	EACH	2	2		
	X0326806	WASHOUT BASIN	L SUM	1	1		
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	97		97	
	X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	100	100		
S	X2501800	SEEDING, CLASS 4 (MODIFIED)	ACRE	1.25	1.25		
S	X2501820	SEEDING, CLASS 5 (MODIFIED)	ACRE	1.25	1.25		
	XX006345	TURBIDITY BARRIER	FOOT	140	140		
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2,357	2,357		
	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	75	75		
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,495	1,495		
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	145		145	
	Z0065000	SETTING PILES IN ROCK	EACH	6		6	
	Δ Z0076600	TRAINEES	HOUR	500	500 *		

FILE NAME = P:\CBEL\WEST\Projects\2009\05-0082\Bolsam_Plan\Drawings\Shets\000_03.dgn

$\Delta=0042$

* CONSTRUCTION CODE 0042



USER NAME = #USER#	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE = 11/9/2010	CHECKED -	REVISED -
	DATE - 10/22/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 5	OF 73 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2332	03-14185-02-BR	KANE	73	5
CONTRACT NO. 63521				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				