SPECIALTY ITEM	SPECIAL PROVISION	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE RECONSTRUCTION, CAPACITY ADDED 0003
		20101100	TREE TRUNK PROTECTION	EACH	10	10
		20101200	TREE ROOT PRUNING	EACH	10	10
		20200100	EARTH EXCAVATION	CU YD	200	200
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9767	9,767
		20400800	FURNISHED EXCAVATION	CU YD	999	999
		20800150	TRENCH BACKFILL	CU YD	825	825
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7716	7,716
		21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	200	200
+		25000210	SEEDING, CLASS 2A	ACRE	1.5	1.5
+		25000314	SEEDING, CLASS 4B	ACRE	0.3	0.3
+		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	143	143
+		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	143	143
+		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	143	143
		25100630	EROSION CONTROL BLANKET	SQ YD	7716	7,716
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	159	159
	•	28000305	TEMPORARY DITCH CHECKS	FOOT	252	252
		28000400	PERIMETER EROSION BARRIER	FOOT	3732	3,732
		28000500	INLET AND PIPE PROTECTION	EACH	83	83
		28100107	STONE RIPRAP, CLASS A4	SQ YD	93	93
		28200200	FILTER FABRIC	SQ YD	93	93
		31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	784	784
		31102300	SUB-BASE GRANULAR MATERIAL, TYPE C 6"	SQ YD	42	42
		35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	42	42
		35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	9266	9,266
		40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	470	470
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8210	8,210
		40600300	AGGREGATE (PRIME COAT)	TON	63	63
		40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	1000	1,000
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	114	114
		40600990	TEMPORARY RAMP	SQ YD	114	114
		40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1427	1,427
		40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3097	3,097
		42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	784	784

SPECIALTY ITEM	SPECIAL PROVISION	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE RECONSTRUCTION, CAPACITY ADDED 0003
		42001300	PROTECTIVE COAT	SQ YD	2653	2,653
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1895	1,895
		42400800	DETECTABLE WARNINGS	SQ FT	143	143
		44000100	PAVEMENT REMOVAL	SQ YD	7819	7,819
	•	X44 01198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	18420	18,420
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1309	1,309
		44000600	SIDEWALK REMOVAL	SQ FT	2352	2,352
		44003100	MEDIAN REMOVAL	SQ FT	2186	2,186
		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4759	4,759
		50105220	PIPE CULVERT REMOVAL	FOOT	50	50
		54213447	END SECTIONS 12"	EACH	8	8
		54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5
		54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1
		54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1
		54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	4	4
	•	54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	1	1
	•	54247120	GRATING FOR CONCRETE FLARED END SECTION 21"	EACH	1	1
	•	54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1
	•	54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	4	4
		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1215	1,215
		550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	241	241
		550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	716	716
		550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	775	775
		550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	25	25
		550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	30	30
		550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	68	68
		550A4300	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND - SIZE 30"	FOOT	53	53
		55100500	STORM SEWER REMOVAL 12"	FOOT	132	132
		55100900	STORM SEWER REMOVAL 18"	FOOT	53	53
		55101100	STORM SEWER REMOVAL 21"	FOOT	250	250
		55101200	STORM SEWER REMOVAL 24"	FOOT	83	83
		55101300	STORM SEWER REMOVAL 27"	FOOT	40	40
		55101600	STORM SEWER REMOVAL 36"	FOOT	78	78
		59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	21	21

• PROJECT SPECIFIC SPECIAL PROVISION
DIST. 1 I.D.O.T. DISTRICT 1 SPECIAL PROVISION
KDOT K.D.O.T. SPECIAL PROVISION

© Copyright CMT, Inc.
CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

USER NAME = Matt Baldwin	DESIGNED - PWK	REVISED -	
	DRAWN - ERD	REVISED -	
PLOT SCALE = 1.0000 ' / IN.	CHECKED - KDF	REVISED -	
PLOT DATE = 2/7/2011	DATE - 12/29/2010	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	01-00269-00-CH	KANE	124	4
		CONTRACT NO. 63533		
		ILLINOIS FED. AID PROJECT		

FILE NAME = L:\KANECO\0792683\Dwg\Exhibits\NoEasement\CADD_Sheets\G_500_01.dgn