| SPECIALTY ITEM | SPECIAL PROVISION | PAY ITEM NUMBER | DESCRIPTION | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE RECONSTRUCTION, CAPACITY ADDED 0003 |
|---|---|---|---|---|---|---|
| + | DIST. 1 | 87800200 | CONCRETE FOUNDATION, TYPE D | FOOT | 4 | 4 |
| + | DIST. 1 | 87800420 | CONCRETE FOUNDATION, TYPE E (42" DIA.) | FOOT | 88 | 88 |
| + | | 87900200 | DRILL EXISTING HANDHOLE | EACH | 2 | 2 |
| + | DIST. 1 | 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 22 | 22 |
| + | DIST. 1 | 88030100 | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 4 | 4 |
| + | DIST. 1 | 88030220 | SIGNAL HEAD, L.E.D., 2-FACE, 5 SECTION, BRACKET MOUNTED | EACH | 4 | 4 |
| + | DIST. 1 | 88102717 | PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER | EACH | 4 | 4 |
| + | DIST. 1 | 88102757 | PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER | EACH | 4 | 4 |
| + | DIST. 1 | 88200110 | TRAFFIC SIGNAL BACKPLATE, LOUVERED | EACH | 22 | 22 |
| + | DIST. 1 | 88500100 | INDUCTIVE LOOP DETECTOR | EACH | 1 | 1 |
| + | DIST. 1 | 88600100 | DETECTOR LOOP, TYPE I | FOOT | 1600 | 1,600 |
| + | DIST. 1 | 88700200 | LIGHT DETECTOR | EACH | 2 | 2 |
| + | DIST. 1 | 88700300 | LIGHT DETECTOR AMPLIFIER | EACH | 1 | 1 |
| + | DIST. 1 | 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 12 | 12 |
| + | KDOT | 89000105 | TEMPORARY TRAFFIC SIGNAL INSTALLATION (SPECIAL) | EACH | 1 | 1 |
| + | DIST. 1 | 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1 | 1 |
| + | * | 89502380 | REMOVE EXISTING HANDHOLE | EACH | 13 | 13 |
| + | * | 89502385 | REMOVE EXISTING CONCRETE FOUNDATION | EACH | 8 | 8 |
| | * | X0322054 | REMOVAL OF PRECAST FLARED END SECTION | EACH | 8 | 8 |
| + | KDOT | X0324085 | EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C | FOOT | 1317 | 1,317 |
| | * | X0703200 | CONCRETE ISLAND, SPECIAL | SQ FT | 3029 | 3,029 |
| | * | X5504200 | DUCTILE IRON STRORM SEWER, 12 INCH | FOOT | 20 | 20 |
| | DIST 1 | X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 |
| + | * | X7800605 | URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 887 | 887 |
| + | * | X7800610 | URETHANE PAVEMENT MARKING - LINE 4" | FOOT | 4537 | 4,537 |
| + | * | X7800630 | URETHANE PAVEMENT MARKING TYPE I - LINE 6" | FOOT | 6707 | 6,707 |
| + | * | X7800640 | URETHANE PAVEMENT MARKING TYPE I - LINE 8" | FOOT | 1026 | 1,026 |
| + | * | X7800650 | URETHANE PAVEMENT MARKING TYPE I - LINE 12" | FOOT | 655 | 655 |
| + | * | X7800680 | URETHANE PAVEMENT MARKING TYPE I - LINE 24" | FOOT | 375 | 375 |
| + | DIST. 1 | 80500010 | SERVICE INSTALLATION - GROUND MOUNTED | EACH | 1 | 1 |
| + | KDOT | 86200120 | UNINTERRUPTIBLE POWER SUPPLY | EACH | 1 | 1 |
| | DIST. 1 | Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 11449 | 11,449 |
| | * | Z0013797 | STABILIZED CONSTRUCTION ENTRANCE | SQ YD | 86 | 86 |
| | * | Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 |

| SPECIALTY ITEM | SPECIAL PROVISION | PAY ITEM NUMBER | DESCRIPTION | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE RECONSTRUCTION, CAPACITY ADDED 0003 |
|---|---|---|---|---|---|---|
| | * | Z0018500 | DRAINAGE STRUCTURE TO BE CLEANED | EACH | 5 | 5 |
| + | DIST. 1 | Z0033046 | RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL2 | EACH | 5 | 5 |
| | DIST. 1 | Z0042002 | POROUS GRANULAR EMBANKMENT, SUBGRADE | CU YD | 8392 | 8,392 |
| + | * | Z0073510 | TEMPORARY TRAFFIC SIGNAL TIMING | EACH | 1 | 1 |
| | BDE | Z0076600 | TRAINEES | HOUR | 1000 | ** |
| | * | XX003822 | STORM SEWER REMOVAL, SPECIAL | FOOT | 24 | * |
| + | KDOT | XX005940 | REMOTE CONTROLLED VIDEO SYSTEM | EACH | 1 | 1 |
| + | KDOT | XX007953 | NETWORK CONFIGURATION | L SUM | 1 | 1 |

* PROJECT SPECIFIC SPECIAL PROVISION
** THE CONSTRUCTION TYPE CODE IS (0042) FOR THE PAY ITEM: TRAINEES
DIST. 1 I.D.O.T. DISTRICT 1 SPECIAL PROVISION
KDOT K.D.O.T. SPECIAL PROVISION

©Copyright CMT, Inc.
CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

| | | | |
|---|---|---|---|
| USER NAME = Matt Baldwin | DESIGNED - PWK | REVISED - | |
| | DRAWN - ERD | REVISED - | |
| PLOT SCALE = 1.2000 ' / IN. | CHECKED - KDF | REVISED - | |
| PLOT DATE = 2/7/2011 | DATE - 12/29/2010 | REVISED - | |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 336 | 01-00269-00-CH | KANE | 124 | 6 |
| | | CONTRACT NO. 63533 | | |
| | ILLINOIS FED. AID PROJECT | | | |

FILE NAME = L:\KANECO\0929003\Dgn\Exhibits\NoEasement\CADD_Sheets\G_S00_03.dgn